

Vol. XCV.-No. 22. Established 1845.

NEW YORK, DECEMBER 1, 1906.

[10 CENTS A COPY \$3.00 A YEAR.



This is the type of shovel which will do the bulk of the excavation throughout the can A Powerful American Steam Shovel at Work in a Cut.



Photographs by Underwood & Underwood.

This is the largest cut in the whole canal; over 29,000,000 cubic yards must be taken out.

A View in the Great Culebra Cut.

PRESENT CONDITIONS AT PANAMA.—[See page 403.]

SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO.

- Editors and Proprietors

Published Weekly at

No. 361 Broadway, New York

TERMS TO SUBSCRIBERS

THE SCIENTIFIC AMERICAN PUBLICATIONS

Scientific American (Established 1945) \$3.00 a year Scientific American Suopiement (Established 1976) \$3.00 a year American Homes and Gardens. \$3.00 a \$4.00 a

money order, or by bank draft or check.

MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, DECEMBER 1, 1906.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

THE PRESIDENT AT PANAMA.

The recent visit of the President to the Isthmus of anama was both timely and stimulating. It occurred at a distinctly critical period in the affairs of the canal. Sweeping charges were being made, both in the methods of construction and the system of administration of the canal, the construction being about to pass into the hands of the contractors, and the administration being simplified, placed under one-man control and located definitely and permanently at the Isthmus. To this new departure the visit of President Roose veit lends special significance. Although Mr. Roosevelt spent but a few days on the Isthmus, the time sily employed; and, apart from the encourage ment which was afforded to the employees by the ce of the Chief Executive in person, the President himself has undoubtedly acquired a firmer grasp the situation, and will find his personal ob servations of great value in arriving at future decias on the many difficult points which must arise during the actual work of construction.

The present occasion marks the close of the secon and the opening of the third chapter in the history of the Panama enterprise. The first chapter included the long and exhaustive examination of the physical conditions of the Isthmus, with a view to determining the best location for a canal, and resolved itself main ly into the determination of the relative merits of Nicaragua and Panama. That work in itself was of great magnitude, and involved the creation of vario commissions and boards, and the putting through of costly surveys by large engineering forces. sequent decision in favor of Panama was followed by gotiations for the purchase of the rights and prop erties of the French company, and the securing of the ssary concessions from the Colombian government. Out of the negotiations and seemingly inevitaintrigues that followed, sprang the young republic of Panama, friendly to the United States and anxious to do everything that lay in its power to further, in the way of concessions and agreements, the pro-

The second chapter contains the story of the vast of preparation which was necessary before the actual work of excavation could be put into full swing. The strip of the canal zone, ten miles in width, stretching from ocean to ocean, was found to be a veritable breeding place of disease; unsanitary, ill provided with pure drinking water, and, because the prevalence of yellow fever and malaria, fatal the health of the many thousands of laborers who would have to be crowded upon the work, if it were to be finished on time. During this second period an formed, and under its sanitary corps was systematic methods the canal zone has been cleaned up, yellow fever practically eradicated, and malaria so far brought under control that the zone is now pronounced by engineers of high standing, who have been engaged for a year or more upon the work, to be no more threatening to health than many of our Southern States. Concurrently with the sanitation of the Isthmus, the great problem of housing and ing the canal employees has been successfully solved. comfortable quarters and good board are now ob tainable at reasonable rates.

Another question, equally vital to the success of the enterprise, is that of administration. There is no denying that, here, many mistakes have been made, and that the earlier operations were hampered by a system that was altogether too cumbersome and slow to suit the very special conditions that are to be found at the lathmus. The resignation of the then chief engineer, Mr. Wallace, served to emphasize the fact that, if the best results were to be secured, and the whole of the complicated organization were to work together har-

Scientific American

moniously, the control of it must be placed in the hands of one man, who should be permanently located at the Isthmus, and have absolute authority in all matters pertaining to the construction of the canal. One of the most happy results, of the President's visit has been the signing of an executive order concentrating the authority in the canal construction in one man, and giving him supreme jurisdiction over the heads of the seven departments of the administration. Both the chairman and the department heads will have their residence at the Isthmus, and will be in a position to push the work through without, as before, to make continual references to higher thority located at Washington, many thousand miles The Isthmian Canal Commission, which we understand is also to be reorganized, will make quarterly trips to the Isthmus for the purpose of receiving reports and advising with the chairman and the heads

The third and longest char '-- in the history of the canal opens with the wise decision of the government to undertake the huge task of active construction by contract, and not by day labor supervised by the gov ernment engineers. The SCIENTIFIC AMERICAN has urged that this was the only practical way which this work could be done. Some time may be med before the government and the contractors can decide upon that final form of contract and those stions of price and time which are mutually But once this has been determined, we believe that the canal will be put through steadily to a final completion. Enough has been learned, however, from the preliminary work, to make it certain that Con gress must be prepared for the exercise of great liberality and patience; for the work will undoubtedly cost much more, and take longer by several years to omplete, than was originally estimated.

JAPAN LAUNCHES A LARGER "DREADNOUGHT."

Concurrently with the completion of the trials of the "Dreadnought" comes the news of the launching by the Japanese of a battleship, the "Satsuma," which not only exceeds the British ship in size and power, but seems to have made like that vessel an enviable rec ord in speed of construction. Most remarkable of all is the fact that this, the world's greatest battleship, has been built entirely by the Japanese themselves. More-over, a sister ship is under construction; and we may look at any time for the announcement that she is afloat. The "Satsuma" is given in the telegraphic dispatches announcing the launching, as being of 19,200 tons displacement, in which case she exceeds the "Dreadnought" by fully 1,200 tons. Her horse-power is announced as being 18,000, and her estimated speed is over 20 knots. One or other of these last figures must be in error; either the horse-power is too small, or the speed too great. The most striking fact about this truly enormous vessel is her armam which is to consist of four 12-inch guns carried in two turrets forward and aft on the center line, and no less than twelve 45-caliber 10-inch guns, mounted in pairs in turrets on the broadside. By this arrange ment the "Satsuma" can concentrate two 12's and four 10's ahead and astern, and four 12's and six 10's on each broadside. The Italian Marina Militare, a usually well-informed journal, gives in its last drawings of this vessel, which also credit her with a battery of four 12's and twelve 10's, the latter mounte in six two-gun turrets. The Japanese, as the result of their experience in the war, have concluded that ing less than the 4.7-inch rapid-fire gun is sufficient to stop the large torpedo boats and destroyers, and consequently the "Satsuma" will carry a battery of a of these pieces. In this connection it is worthy that this enterprising nation has four 16,000 ton 22-knot armored cruisers afloat or on the stocks, which will carry four 12-inch and eight 8-inch guns This gives them the as their main battery. offensive power as our own battleships of the "Georclass, and practically places them in the battleship class. Evidently this youngest of the naval powere is determined to remain master of the Pacific

RECENT AERONAUTIC EXPERIMENTS IN FRANCE.

Experiments with aeroplanes and airships are being carried on in the neighborhood of Paris with great activity. M. Bleriot made a trial of his modified apparatus mounted upon a raft upon Lake Enghien. The apparatus glided upon the lake and moved forward by means of the propellers alone. Although the speed seemed to reach at least 20 miles an hour, the apparatus did not rise in the air. The aeroplane weighs some 900 pounds, added to the aeronaut's weight. Bleriot tried to draw the aeroplane and add to the effort of the propellers by means of a rope and motor-driven winch. But it was difficult to make the combination work well, so that after running over the lake, making a number of evolutions, experiments were stopped for that day. M. Bleriot believes his aeroplane will rise if there is a strong head wind, and hopes to fly shortly.

The new Vuia aeropiane which has been also described in these columns is being tried on a meadow near Paris. It will be remembered that the canvas body of the aeropiane is mounted on a carriage of metal work and runs upon wheels over the ground by the propellers. Should the power be great enough, the whole apparatus is lifted off the ground and is urged forward by the propellers. During a trial held in the presence of the Aero Club's officials, there was a strong head wind of 20 feet per second. Heading the aeropiane against the wind, the aeronaut set the propellers running and made a good speed over the ground. Accelerating the speed, the aeropiane left the ground and made a flight of a short distance, then alighted and again made a second rise in the air. The distances were short, however, in each case. Vuia uses an angle of 5 degrees with the air. Owing to a slight breakage, the apparatus was not in shape to continue, but a new flight will be made shortly.

Count de la Vaulx is preparing for a new series of flights with his airship of the cigar-shaped pattern. He is operating over a well-located piece of flat ground to the west of Paris, and here he erected a balloon shed of great size in order to carry on the work. He expects to make a flight within a short period over the plains which surround this locality.

It will be remembered that the engineer Leger in

It will be remembered that the engineer Leger in constructing a flying machine of the helicopter form for the Prince of Monaco. This has been carried on at Monaco with great secrecy, so that no details of the new flyer have as yet been made public. It is to use an "Antoinette" four-cylinder motor, built by Levavaseur, of Paris, of the same pattern as that used by Santos Dumont. But here no less than four such motors are to be mounted for driving the propellers. The experiments will no doubt take place about the first of December at the Chateau of Marchais, belonging to the Prince of Monaco.

After making his celebrated flight of October 23, Santos Dumont now considers that he is well enough advanced to be able to steer the aeroplane in any direction. Accordingly he made an entry for the Deutsch-Archdeacon Grand Prix of \$10,000 at the Aero Club, as he expects to make an attempt at winning this prize. It is awarded to the first flyer without balloon which makes a closed circuit of 1 kilometer (0.62 mile) during the day without touching ground, turning around a point selected in advance by the competitor and distant at least 0.3 mile from the starting point. Any number of attempts can be made during that day. These must be made in the presence of the Aero Club's commission. Santos Dumont has selected a spot of ground in the Bols de Boulogne, where he made his first flights with the aeroplane. The machine has been overhauled in the meantime.

ENGLISH AEROPLANE PRIZES,

The London Daily Mail has offered a prize of £10,000 (\$50,000) to anyone who travels by aeroplane from London to Manchester in one day, two stoppages being allowed for the taking in of gasoline. The competitors must be members of a recognized aero club. But if any difficulty is made by an aero club in admitting mechanics or other worthy persons to membership, it will be seen to that a suitable club is formed in England, which club will be accepted as an aero club.

Spurred on by the Daily Mail apparently, the proprietor of the London Daily Graphic and the Graphic offers £1,000 (\$5,000) to the inventor who first produces a machine which, being heavier than air, shall fly, with one or more human passengers, between two given points not less than one mile apart. The points of arrival and departure will be selected by the proprietors of the Daily Graphic and the Graphic.

The Adams Manufacturing Company announce that they will give £2,000 (\$10,000) to the winner of the Daily Mail's £10,000 (\$50,000) prize, provided his aeroplane be made entirely in Great Britain or her dependencies over seas.

The proprietors of the Autocar offer £500 (\$2,500) to the maker of the gasoline engine driving the flying machine which wins the Dally Mail prize, provided the engine be made by a British automobile manufacturer.

The true student of the professional or technical school becomes heir to a comprehensive and clear understanding of his duties and responsibilities in his relations to his fellow men and to the community. Those duties and responsibilities present themselves to his trained mind in their real proportion. He is neither non-developed nor mal-developed in his judgment of affairs. His university training, especially in the technical school, has taught him accuracy and penetration in the analysis of any proposition confronting him, and that truth and knowledge must be sought with the directness of a plumb line. Science yields nothing but confusion to the shifty, devious, and dishonest inquirer. The fundamentals of morality are the very stepping stones to technical success or professional attainment.

THE HEAVENS IN DECEMBER.

BY HENRY NORRIS RUSSELL, PH.D.

We spoke last month of the fact that when Venus is nearly between us and the sun, the horns of her crescent extend beyond their usual positions, so that it sometimes covers three-quarters or more of the

This could not happen if the planet had no atmosphere, for in that case just one-half of her surface would be lighted by the sun, and her crescent, though varying in breadth from time to time, would always cover just half her circumference (as is the case with the moon).

But if Venus has an atmosphere, we can account for these observations. An atmosphere will extend the illuminated part of her surface in two ways. It will refract the sun's rays (like a lens) so that they are bent enough to reach the surface at points which were previously in darkness, and even beyond the limit of this action the upper layers of the atmosphere will still be illuminated, though the surface below them is dark. (This is what causes twilight on the earth.) In the same way we will see more than half the planet's surface, and still more of her atmosphere. The result of this is to extend the crescent, as observed. For suppose we were behind Venus, and so near that she completely hid the

sun. In the absence of an atmosphere, she would appear quite dark (as the moon does during a total eclipse of the sun). But if there is an atmosphere, it will be illuminated by sunlight from behind (which fails to reach us). and the planet will seem to be surrounded by a luminous ring. Now sup pose the sun to move off to one side. The part of the ring farthest from the will gradually fainter, and will finally disappear, leaving a cres cent, which however at covers nearly the whole circle, and gradushrinks down to smaller dimensions as the sun moves away.

This is just what is actually observed (except of course that we cannot get near enough to Venus to make her hide the sun).

From the amount of extension of the horns of the crescent we can calculate how far the twillight in Venus's atmosphere extends. In this way it is found that her atmosphere must be much less extensive than ours, for the brighter part of her twilight extends only about one degree on her surface, and the fainter part about three degrees more, while on the earth the corresponding amount is ten degrees or more.

It is therefore certain that, while Venus undoubtedly has an atmosphere,

edly has an atmosphere, the earth has much more, and as seen from Mars, would present a similar appearance, but in an increased degree.

THE HEAVENS

Our map shows the general appearance of the sky at the times indicated upon the margin. The brilliant winter constellations are now appearing in the east. Orion is well up, and the line of his belt points down to Sirius, which has just risen, and up to the red Aldebaran, in the constellation of the Bull. The Little Dog with the bright star Procyon is low down due east, and higher up, on the left, are the Twins (Gemini) which are now made more brilliant than usual by the presence of Jupiter. Above them in the Milky Way is Auriga, the Charioteer, and the great yellow star Capella.

Following along the Galaxy we reach Perseus, then Cassiopeia, next Cepheus, and finally Cygnus and Lyra, low down in the northwest.

The Dragon and the Little Bear are in the northern eky, west of the Pole, and the Great Bear is coming up to the eastward.

In the southwestern sky we see Aquarius the Water Hearer (who now bears the planet Saturn as well) and the Southern Fish with the lonely bright star Fomalhaut. Higher up is the great square or Pegasus, and

Andromeda is right overhead. Below it, south of the zenith, are Aries the Ram and Pisces the Fishes. Below this again is Cetus the Whale. Its principal stars are shown on the map. One of them, o, better known as Mira, is a very remarkable variable star. For most of the time it is of the ninth magnitude, requiring a small telescope to see it, but at intervals of eleven months it brightens up enormously till it is of the third or fourth magnitude, and fully two hundred times as bright as it was six months before.

The star is now in one of these maxima (having increased rapidly in brightness in October) and is easily visible to the naked eye. It will be interesting to watch its fall in brightness, which will probably make it invisible to the unaided vision in a month or two. Below Cetus is the still larger constellation Eridanus, which begins close to Orion and runs with many curves down to our horizon and below it. The last of its conspicuous stars which we see, \$\theta\$, has an interesting history. It was described by an Arabian astronomer, Al-Sufi, who lived about the tenth century, as of the first magnitude. As his other observations are very accurate, there is no reason to doubt his statement, and it seems that this star has lost about five-sixths of its brightness in the last thousand years. A first-magnitude star farther south, invisible in our latitude

away on the 1st and the 28th. She is in conjunction with Jupiter and Neptune on the 3d, Mars on the 11th, Venus and Mercury on the 14th, Uranus on the 16th, Saturn on the 20th, Jupiter and Neptune once more on the 30th.

At 1 P.M. on the 22d the sun reaches its greatest

At 1 P.M. on the 22d the sun reaches its greatest southern declination, and enters the sign of Capricorn, and in-aimanac parlance "winter commences."

THIELE'S COMET.

A comet visible in a small telescope was discovered by Holger Thiele, of Copenhagen, on November 11. It is in Leo, in R. A. 9h. 25m., declination 15 deg. north (on November 13) and is moving northeast at the rate of about 1½ deg. a day. Its orbit has not yet been computed, so it is impossible to predict its position in December


Princeton University Observatory

PEAT IN ITALY.

One of the greatest handicaps to the development of commercial industries in Italy is the lack of native coal supplies, due to the fact that the country is peculiarly deficient in workable coal deposits. Every ton of coal has to be derived from foreign sources, the annual imports exceeding 5,000,000 tons. It will thus be seen that the situation of the country is a serious

one, since in the event of a war its safety would be gravely imperiled. There are, however, scattered over the country enormole acattered tracts of peat bogs; and realizing the seriousness of the national position, and the fact that almost almost illimitable quantities of peat are immediately available, the government endeavoring to turn these present wastes profitable account. A bill has recently been passed by means of which every possible encouragement is extended for the development of a process for the conversion of peat into a satisfactory fuel, and to stimulate and foster the commercial development of any practicable sys-tem that may be devised. The formation of large companies for the utilizaadvocated, and several inwhich amount at least one Italian Italian Itself would be an this connection the

tion of peat and lignite is ducements are held out, such as the remission of duty-free import of machinery, and free registration. Any company, however, that is founded must have a minimum capital of \$570,000, of of fourth must be reserved subscribers. government tensive purchaser, and in panies must extend their business in such a manner that they will be in the position to hold 50,000 tons at the disposal of the government in the year operations are comme In the third year this reserve is to be increased to 200,000 tons, and in the seventh year to no less than 500,900 tons. Though the government would thus probably constitute the largest purchaser, the terms upon which the fuel is to be purchased must be ten per cent less than the prevailing market price. Notwithstanding



In the map, stars of the first magnitude are eight-pointed; second magnitude, six-pointed; third magnitude, six-pointed; third magnitude (a few), four-pointed; fifth magnitude (very few), three-pointed, counting the points only as shown in the solid outline, without the intermediate lines signifying star rays.

(or in his) now goes by the name of Achernar, which Al-Sufi bestowed upon Theta Eridani.

THE PLANETS.

Mercury is morning star in Scorpio. On the 18th he is at his greatest elongation from the sun, and rises at about 6 A. M. Venus is also morning star, and is better seen at the end of the month than at its beginning, when she is very near the sun. On the 13th she is in conjunction with Mercury. Mars is likewise a morning star. He is in Virgo, and rises at about 3:30 A. M. on the 15th.

Jupiter is in opposition on the 28th, and is the brightest object in the evening sky. Transits or eclipses of his satellites occur almost daily, and afford a very interesting telescopic spectacle.

Saturn is in Aquarius, and is in quadrature with

Saturn is in Aquarius, and is in quadrature with the sun on the 1st, so that he comes to the meridian at 6 P. M.

Uranus is in conjunction with the sun on the 30th, and is consequently invisible this month. Neptune is in Gemini, and will be in opposition early in January.

THE MOON.

Last quarter occurs at 9 P. M. on the 9th, new moon at 2 P. M. on the 15th, first quarter at 10 A. M. on the 22d, and full moon at 2 P. M. on the 30th.

The moon is nearest us on the 15th and farthest

Noiseless Steam Engine Exhaust.

peat fuel has been devised

these inducements, however, no results have yet been attained, as no suitable process of manufacturing the

The gas engine is not the only offender in the matter of noisy exhaust. Muffling tanks to minimise the noise of the escape of exhaust steam from high-pressure non-condensing steam engines are sometimes needed. In such cases it suffices to insert near the engine a tank of 15 or 20 times the volume of the cylinder and continue the exhaust pipe from this muffler. This will do away with the disturbance caused by high-pressure exhaust steam passing through a tortuous exhaust pipe.

No oxidizing solution is equal to chloride of platinum for oxidizing silver. The deposit is extremely black and very adherent.

the sheet might

groundto transpar. ency, but the

After a ser-

ies of failures

along these lines Mr. Col-

his attention

to the manu-

facture of win-

dow glass by

machine cylin-

der processes

and after expending

fort in this di-

rection he finally succe

in constructing

able glass of uniform

strength which machine

is probably

the best 'cylin-

machine which pro-duces market-

of-

siderable

directed

have be

additional pense was pro-

hibitive.

burn

thickness, surface, and polish. Naturally, his first thought when assailing the problem was to pass the

plastic glass between heated rollers (Fig. 3), but it

was soon found that while it was possible thus to produce sheets of desired width and thickness, the

THE FIRST MACHINE FOR THE COMMERCIAL PRO-DUCTION OF WINDOW GLASS BY THE SHEET PROCESS.

The manufacturing of window glass is one of the few arts which seems to have resisted all efforts of the keenest mechanical intellects to raise it above a handicraft which involves much costly and cumbrous human labor, to the dignity of an automatic process. Ever since panes of glass have been used in buildings. but three manufacturing methods have been employed, vis., the crown process, the hand-blown cylinder pro-

cess which displaced it, and machine blown cylinder The hand - blown cylinder method, by which the bulk of glass window glass is made at the present time, not only simple, but almost primitive in its crude ness, notwithstanding that it requires skill and strength part the of the workmen The wages paid such skilled workmen are highor than those for almost any other class of labor. By re peated gatherman, technically known as a

gatherer, collects a ball of plastic glass on the end of blowpipe, as shown in Fig. 1a. The gatherers pass the balls to workmen known as blowers and snappers who block and shape the mass. By the sheer his lungs, the blower inflates and shapes the glass until it forms a sphere of some size (Fig. 1b); then elongates the bubble while swinging it in the swing hole (Fig. 1c) until it has chilled. This partially completed cylinder is now reheated, and by repeated blowing and manipulation is finally brought to its desired shape and length. The lower end of the cylinder is then warmed and blown open. Thus a ball of glass is inflated to a cylinder, which is usually our to eight feet in length, according to the d sired dimensions of the finished sheet. In order to

ordinary flat window glass, the cylinder is eked from the blowpipe. the severed from t h e cylinder proper with a thread of redhot glass (Fig. The cyl 14). inder is next cracked length wise with hot iron (Fig. 1e) and plac ed in an over where it for heated, flatten (Fig. 1/), and annealed. is then washed and out.

The only suc cessful effort which has been

made to improve on this ancient process is recorded in the introduction of machinery for drawing and blowing the cylinders. As a matter of fact, the only machine-made window glass produced to-day is made by this means. The process simply substitutes men wn as ladlers, machine blowers, and tenders for the gatherers, blowers, and snappers. A high degree of skill is required to manipulate and control the blowing and drawing apparatus properly. The other operations are identical with those of the hand-blown process. There is, however, a small saving in the

cost of production by the machine over the hand cylinder process. Although it substituted a method, me chanical in some of its stages, for the production of cylinders, it is not considered an important advance in the art.

It must not be inferred that the proprietors of the large works have not been alive to the deficiencies of the older methods of making glass; for ever since machinery became a potent factor in modern industries, they have endeavored to create a practical process for drawing glass sheetwise from the molten ma-

glass was not marketable because its surface chilled on coming in contact with even the most fervid rollers, so that instead of exhibiting the limpid transparency and high fire polish so much desired, it resembled frosted glass in appearance. The effect was produced by infinitesimal surface marks, or cracks. Obviously,

ses, and Partially Successful Attempts to Produce Glass These Illustrations Show the Old and New Cylinder Proces by the Sheet Process.


terial. Numerous costly experiments have been made in this direction, but up to this time all have ended difficulty of maintaining the width of the sheet as the difficulty it was drawn from the pot or working chamber. Molten glass like all viscous substances tends to narrow down to a thread as it is drawn, and all attempts to maintain the width by gripping the edges of the glass with clamps or pincers as it emerged from the mass proved impracticable. Somewhat more ingenious so far as holding the width of the sheet is concerned, but unsuccessful as a whole, is the scheme which is roughly illustrated in Fig. 2. It consists in forcing the glass through a slit in the bottom of a fireclay vessel and drawing it upward. Whenever the surface of the

der machine thus far invented. This statement is made because the cylinder can be removed from the pot of moiten glass without contaminating the contents of the pot The machine has with fragments of chilled glass. The machine has a double drawing pot, so that the machine blower is enabled to draw successive cylinders, the surface of the glass in the idle pot being reheated while its companion pot is producing a cylinder. This design of apparatus dispenses with the ladler, the glass being kept at a constant level in the drawing pot, by being continuously fed from the melting furnace. this is accomplished may be seen in Fig. 4. The pot is formed with a central cone of fireclay, upon the apex of which the tapering end of a cylinder is ulti-mately held. By means of a blast flame the com-

paratively thin glass bond that ties the cylinder to the co is melted away, and thus the pollution of molten glass in the working pot by fragments of glass is avoided, making it possible to co tinue the drawing of suc sive cylinders from the sa pot-a feat which has not been herete fore accomplished. Efficient as

this method of producing cyl-inder glass is, it of a machine

by means of which glass can be drawn out in continuous sheets. Returning to the task of producing 8 machine which would produce glass without first blowing it into cylinder form, Mr. Colburn hit upon the method illustrated in Fig. 5. In this plan spheres of fireclay are employed, carried on the ends of long arms which are immersed in the glass and which are made to revolve upwardly and outwardly, and away from the two edges of the sheet. These spheres impart au out-ward motion to that portion of the surface of the (Continued on page 403.)



THE COLBURN MACHINE FOR MAKING WINDOW GLASS BY THE SHEET PROCESS.

glass touches any substance directly, it can never b drawn into sheet glass free from surface marks, such as is required in marketable window glass.

By far the most systematic and painstaking study which has been made of the whole problem we owe to Mr. Irving W. Colburn, of Franklin, Pa. He has attacked it on every conceivable side, expended large sums in experimenting, built and destroyed machine after machine, and after eight years has produced the first commercially successful apparatus for drawing sheet glass of any reasonable width and of desired

ol-

n-Ma X-M

g.

di-in-ed

ng n e

ro

of

ine ly

ine

wer

its

ign

the

ulti-

that

thu n of

ot by

void-

om.


short tinu ng a n the

Scientific American

THE INTERIOR CONSTRUCTION OF A PIANO PLAYER.

It is not stating the case too strongly to say that the introduction of the first successful plane player, which event occurred about a dozen years ago, was, in its educational effects, the most important development in the musical world of the last century. For the average lover of music who may be desirous of

Fig. 1.—Transverse Section, Showing the Mechanism and Operation of the Player.



The complete action is placed in the central air-tight chest, and tested until it is

Fig. 4.-Jack for Testing Player Actions.



Fig. 6.—Press for Gineing Sheepskin Diaphragms on the Power Pneumatics.

becoming himself a performer, it will not be disputed that the piano is the most available and popular instrument. And yet the amount of laborious preparation that is necessary before anyone can become even passably proficient as a pianist is so great, and before one can become reasonably expert is so enormous, that the majority of the workaday people of this world have at their disposal neither the time nor

the funds that are necessary. For the average amateur, by far the greater part of the labor entailed in learning to play the piano is spent in acquiring the manual dexterity which is necessary merely to strike the notes in their proper consecutive order and time; that is to say, to acquire the mere mechanical technique, irrespective of those shadings of time and expression which give life and color to the work of the finished planist.

With the production of the first succe ful piano player, it became possible for any-body, whether he possessed any musical taste or not, to play any musical compo-sition with absolute fidelity to the written score, at least as far as the striking of the notes in their proper order and time is concerned. Because of this extremely clever mechanical invention, it was no longer necescerned. sary to spend the years of time and the not inconsiderable sum of money that must formerly be spent to acquire even the most elementary technique. That the production of the mechanical player had filled a longfelt need was proved by the world-wide popularity which it instantly achieved; and even the musical critics and the virtuosos themselves, who at first looked with contempt upon this mechanical contrivance, have now come to realize and freely admit that it is one of the most powerful educational forces to be found in the world of music at the present day. That it had its limitations was not denied, even by the various makers themselves; but it is claimed, and not to be disputed, that these imperfections have been largely eliminated. When we remem ber that, in point of years, the mechanical player is yet in its infancy, it is reasonable

to expect that, when t h e interpretative devices shall have been perfected, the instrument in the hands of a musician will rival the playing of any but the most skilled performers by hand.

Its In view of present remarkable popularity and the industry which it has produced, there is food for thought in the fact that the piano player has had but a little over a single decade of commer-cial life. The Unit-States Census ort says: "In ed Report says: "In 1895 Messrs. Wilcox & White, of Meriden, Conn., began manu facturing an inter-

for attachment, and in February, 1897, built their Angelus cabinet piano player. This instrument, the invention of E. H. White, may be regarded as the pioneer of various similar attachments which have since been placed on the market." Because of its priority, we have chosen this instrument to form the basis of the present article, in which we shall endeavor to show the interior construction and operation of this most interesting device.

INTERIOR CONSTRUCTION .- Turning then to the accompanying transverse sectional view (Fig. 1), taken through the player, we find that it consists broadly of a pair of foot bellows for exhausting the air, a series



Fig. 2.—Sectional Model, Showing Tracker Board, Tubes, Primaries, Secondaries, Diaphragm Pneumatics and Striking Fingers-



Fig. 3.-The Tempo-Control Mechanism.

This shows the 130 pecksts for the primary and secondary pro-

Fig. 5 .- The Well-Board.



Fig. 7.-Milling Out the Teeth in a Set of Plangers. THE INTERIOR CONSTRUCTION OF A PIANO PLAYER,



-One of Several 11-Stang Brills, Boring Fig. 8. Air Ducts in Edge of Well-Board.

of delicately-balanced poppet valves for regulating the flow of air, a series of small bellows governed by these valves, one to each key of the piano keyboard and a set of fingers operated by these bellows (or pneumatics, as they are technically known), for strikthe piano keys. And just here it should be explained that the power which strikes the keys is pro fuced by suction and not by pressure, the object of the foot bellows being to produce the vacuum, which is utilized in operating the little striking bellows in their proper order

The foot bellows A operate, by means of the levers B, two large exhaust bellows C, which exhaust the air,

as indicated by the arrows, through the passage D. from an air-tight chest E E. This chest extends across the full width of the player, and it contains within it the whole of the "action" The action consists of sixty-five complete sets of mechanism of the kind shown in our sectional view and in Fig. 2, there being a complete set to each key of the piano that is to be played. Each set consists, as we stated above, of certain little poppet valves regulating the flow of the air, and a power pneumatic which, by its inflation and deflation, serves through connect ing levers to operate the striking fingers, which

do the playing on the keyboard.


The front face of the air-tight action chest E is closed by a board O, which is pierced at its upper edge by sixty-five air ducts P, each of which provides an independent passage from the outside air down to its own set of poppet valves, or pneumatics, as they are called. Normally, these ducts are closed by a sheet of music Y, which is adapted to be drawn across the tracker board, as it is unrolled from one and rolled on to the other of two spools carried on opposite sides of the tracker board.

OPERATION OF THE PNEUMATICS.-When a piece of music is to be played, the air is exhausted by means of the foot pedals, and the vacuum produced causes the little motor Z to operate the spool X' and draw the music sheet from left to right over the tracker board. In the normal condition, that is, before the perforations in the music sheet reach the holes in the

tracker board, the whole of the action chest is subject to partial vacuum, proportionate to the strength of the pumping, and all of the power pneumatics, H F, are the deflated condition. and the corresponding strik ing fingers are in the raised position. The instant, however, that a perforation in the sheet reaches the duct P. there is a rush of air down this duct to the under side of a little flexible and airtight piece of thin leather, known as the primary pneu-matic,, which rises and lifts a little poppet valve Q. The button on the bottom of this valve closes against the cuum, and the button the top of it rises, opening a channel X, which is in connection with the outside air. and allowing said air to rush through channel R to the under side of a larger secondary pneumatic 8. This. in turn, rises; closes the bottom button of the poppet valve T against the vacuum; lifts the upper button and puts the channel U, which is open to the outside air, in communication with the pass-The air rush through this passage and up through a series of ducts W into the interior G of the large dlaphragm power pneumatic, or striking pneumatic, H. Now, this pneumatic being in the vacuum action box E, the entrance of the air

it to expand suddenly, driving the disk I forward, or outward, and operating the lever J. The horizontal arm of this lever lifts a poppet but ton K, which in turn raises the notched plunger L. This plunger engages the inner end of a pivoted striking finger M, causing the outer end to descend sharply and strike the plano key N. The plano key will re main depressed until the perforation in the music roll has passed the duct P, and the latter is closed again by the paper. Closing the duct P causes the primary and secondary valves and the whole of the action to resume their normal positions, ready for another blow. From this description it will readily be apparent that, by cutting perforations in the music roll to correspond position and in length with the particular keys to be struck, and with the time during which they are to be held down, the music of the piano score can be reproduced with mechanical accuracy, as far as the striking of the proper notes, and the time during which they are to be depressed, is concerned.

THE DIAPHRAGM PNEUMATICS.—It will be seen from the above description that the whole of the action is inclosed in a vacuum chest, where the delicate little valves are entirely protected from dust, and the irritating rattling of these valves in their rapid movements, which is noticeable in some forms of players, is so



atics which do the striking. Below them are seen the

Fig. 9.-A Complete Bank of 65 Diaphragm Power Pneumatics.

completely muffled as to be inaudible. Furthermore the fact that the action operates in a partial vacuum assists not a little in that rapidity of action which is of such vital importance where rapid repetition note is necessary. The peculiar construction of the diaphragm pneumatic, which, as we explained above, does the actual striking of the keys, is one of the dis-tinctive and most important features in this style of In other players the power pneumatics are of the hinged-bellows type similar in form to the large pumping bellows, CC, as shown in the drawing; and under the heavy duty that is required of them,



naic roll. Here shown with the pedals drawn out ready for use with the piano

Fig. 10.-Piano Player and Piano-Front Removed. THE INTERIOR CONSTRUCTION OF A PIANO PLAYER,

are liable to crack at the edges, and cause a leakage of air. The form of pneumatic here shown has been designed to obviate this difficulty, and also to provide greater sensitiveness and speed of action. It consists of a block of quartered poplar wood 2% inches wide by 5% inches high and % of an inch thick. It contains a recessed pocket G, provided with five ports, W, for the admission of air. The recessed chamber is closed by a disphragm of specially tanned and very thin and flexible sheepskin, which is glued down upon the face of the block in such a way as to provide an air-tight inclosure, but yet allow the sheepskin to be sucked into the cavity, or distended above it, by the alternate admission or expulsion of the air into the pneumatic. By this arrangement the sheepskin is not subjected to any sharp creasing or folding, and its life is indefinitely prelonged. On the outside of the st skin is a thin disk of wood I, which bears against the lever J. The flexibility of this skin and its small inertia render the action of the pneumatic also very sensitive; and acting as it does in a vacuum, it is capable of a rapidity of repetition which is really remarkable. By way of testing the rapidity and durability of the diaphragm pneumatic, an Angelus player was recently installed in an exhibition room of this city, and run continuously ten hours a day for several

months, during which period each of a dozen of the diaphragm pneumatics was operated 70. 000,000 times at an average speed of 600 strokes per minute, without showing, at the end of that time, any appreciable evidence of wear.

INTERPRETATIVE CONTROL.—The mechanism of

the instrument as thus described, has to de with the mere striking of the notes independent. ly both of the force with which they are struck and of the tempo. If the capabilities of the and of the tempo. instrument stopped at this point, the playing would be entirely automatic, mechanical, and uninteresting. To bring the instrument up to the point at which the operator can impress upon it his own individuality in controlling the tempo and the tone according to his interpretation of the music, was the most difficult task confront-

ing the inventor, and in proportion as this in-terpretative control is secured, is an instrument entitled to rank in the first class.

EXPRESSION, OR VOLUME OF TONE,-The expression volume of tone, is dependent upon the degree of strength with which the notes are struck, and this should vary from the softest pianissimo to the strongest fortissimo. It is secured by the use of two se called melody pistons operating upon the choking boxes, one for the bass, the other for the treble, through which the air must pass as it enters to inflate e diaphragm pneumatics. The entrance of the air these boxes is controlled by two valves, U^z and U^z . the diaphragm pneumatics. When the music is being played softly, valve U^s , which is controlled by hand, is kept

closed, and the air flows through valve U^3 . The degree of opening of U^3 is c trolled through a bent rod U' attached to and operated by choker pneumatic Us, degree of closure of this pneumatic being determined by the suction of the main bellows, with which it is con nected. The object of this choker is to render the flow of air to the diaphragm pneumatics independent of the strength with which the main bellows are being worked; for if the operator is pumping hard and the suction is strong, the pneumatic will be choker sucked down upon the inlet valve U, throttling it, and maintain ing the moderate inflow of air which is necessary when playing softly. When it is desired to play more loudly, the operator, by releasing the rod U° , opens the valve U° and allows the outside air to flow directly to the dis phragm pneumatics, independently of the choker pneumatic U°. The air chamber is divided at its center by a transverse diaphragm, and a choker is provided for each half of the chamber. enables the player to strike the keys on either the lower or upper half of the register greater emphasis, and give to the theme or melody cording a stronger accent as it happens to lie in the up-

per or lower half of the keyboard.

TEMPO CONTROL.—The control of the tempo depends upon the speed with which the music sheet is drawn by the rotating spool across the top edge of the tracker board, and the speed of the spool is determined by the speed of the little five-crank suction motor & which drives the spool by means of chain and sprock ets. The speed of the motor is controlled by a small slide valve, which is set by the operator at the tempo indicated on the roll. Now, it will be evident that since the speed of the motor will depend upon the strength of the air suction, it is necessary to provide some form of governor which will maintain that

ill

to

en-

on

ined

nain

agm

cked

tain

it is

e U

dia-

er by

trike

gister and elody rding

pends |rawn

acker ed by or Z.

that n the rovide t suo

tion at an even tension; otherwise, the music sheet would be run slowly when the bellows were being pumped softly, and too fast when they were being rumped vigorously. The governor which has been devised for this purpose is one of the most ingenious of the devices controlled by the makers of this player. It is a self-choking device of the same principle of action as that used in the two expression control chok ers, above described. It consists of a pneumatic, which is interposed between the bellows and the motor, and serves automatically to throttle the flow of air through the motor, closing when the tension is high, and opening when it is low. The equilibrium thus automatically secured causes the motor to run evenly at the desired tempo, whether the instrument is being played loudly or softly.

PHEASING LEVER.—Another important device, peculiar to this instrument, which assists greatly in allowing the operator to impress his personality on the music is a little rocking lever placed on the ledge just below the piano keyboard on which the tempo and the choker box levers are also arranged, which acts directly upon box levers are also arranged, which acts directly upon the tempo governor pneumatic, and enables the player, by depressing one end of the lever, to instantly close the governor valve to any extent he desires, and slow down the music, proportionately, even to a full stop. By depressing the other end of the lever the tempo may be accelerated. It is claimed that the interposition of this direct control through the phrasing lever has done more than anything else to break up the mechanical effect, and bring the operator as nearly as possible into the position of having his hands directly upon the keyboard itself.

The sustaining or "loud" pedal is operated through the member a and the levers b and C, by a lever placed conveniently to hand among the various operating levers on the ledge below the piano keyboard. In concluding our description of this interesting de

vice, it should be noted that this player was the first to be installed within the plano case itself. In fact, the first player was of this character. Subsequently, in or-der to enable existing planos to be played, the inder to enable existing planes to be played, the instrument was set up in a separate cabinet case. Today, however, the obvious advantages of having a
piano which is available for use either by those who
play by hand, or those who play by the music roll,
are likely to render the company's first style of player
the prevailing and permanent type. the prevailing and permanent type.

THE FIRST MACHINE FOR THE COMMERCIAL PRODUC-TION OF WINDOW GLASS BY THE SHEET PROCESS.

(Continued from page 400.)
molten mass lying adjacent to the edges of the sheet, thereby counteracting that tendency to shrink and draw to a thread which is the property of all such materials, and which has rendered the problem of devising a sheet machine so difficult of solution. By this means he was enabled to draw continuously sheet glass of any desired width and of a thickness varying at the will of the operator from 1-16 to ¼ of an inch. Complete success was not, however, immediate. Ribs or wave-like lines or strize were formed upon the surface of the finished product in some unaccountable way. These were very minute, but still pcrceptible enough distort the visual rays and to produce unpleasant refraction. Although the use of the spheres had over-come the difficulty of maintaining the width of the sheet, still the presence of the wave lines was so serious a defect that it became absolutely necessary to remedy it. An elaborate study of the conditions which caused these formations was low undertaken. After observations and experiments extending over a year, it was discovered that the defect was due to several causes, among which was the tendency of the glass to receive on its surface impressions from the rough side walls of the pot, particularly if the point at which the glass left the walls was only a few inches from the point at which the glass entered the sheet. Moreover, the chilling influence of the atmosphere on the surface of the glass, while molten in the working chamber, caused it to lie dormant in spots and also to wrinkle slightly. These defects were hardly perceptible to the eye, but existed nevertheless, and erre bound to cause the disastrous wave lines when the glass entered the sheet form. Dust particles dropping into the working chamber were also a source of serious trouble. It seems that such particles, however minute, adhering to the surface of the molten mass, are gradually incorporated in the sheet, and the blemish made by them is elongated so as to produce a wave, line, or cord. Mr. Colburn found that by placing near and on each side of the sheet a rotating fireclay cylinder D, slightly immersed in the molten mass (Figs. 6 and 7), and at the same time superheating remote portions of the glass, the difficulties were overcome. These rollers are rotsted in opposite directions during the operation of drawing the sheet of glass, and serve not only to impart movement to a portion of the surface of the molten mass away from the faces of the sheet during the drawing operation, but also to determine the area of the surface in the working chamber or pot, which is

more or less exposed to the cooling influences of the atmosphere, the superheating occurring on that portion of the surface of the moiten mass to the rear of the rollers. These rollers make but one revolution in from ten to thirty minutes, depending upon existing conditions, and serve also as a most perfect equalizer of temperature of the molten glass in the working chamber, which is an absolutely necessary factor in drawing an even thickness of sheet glass. A film of plastic glass adheres to these rollers and is carried upward and over the rollers, chilling slightly in the chamber A, because of the presence of the water jackets C C, which are inserted, one on each side of the emerging sheet of glass. These jackets are not designed to chill or thicken the sheet, but merely to acreen off the heat radiating from the revolving white-hot clay rolls. The plastic film of glass on the roller- melts off entirely in the superheating chambers $B\ B$.

As the sheet of glass is drawn from the mass of glass lying between the rollers, and as the spheres impart an outward movement to that portion of the surface of the mass lying immediately adjacent to the edges of the sheet, the following effects are observed: The molten glass at and just beneath the surface adjacent to the edges of the sheet moves outwardly and away from the central line of the sheet, thus serving to hold the sheet to its full width. As the sheet moves upward there is drawn into it some of the surface por tion of the molten mass immediately adjacent to its two faces, and also some of the molten glass beneath the surface. The skin or surface portion of the glass in the working chamber adjacent to the sides of the et being drawn, becomes the skin or surface of the finished drawn sheet. Simultaneously the two rollers on opposite sides of the sheet of glass skim some of the surface portion of the molten glass lying between the rollers and the sheet of glass away from the sheet. The result of the combined action of the drawing of the sheet and the movement of the rollers is a constant skimming of the molten glass lying between the two rollers, so that a fresh portion or a new surface is stantly being exposed to the cooling effect of the atmo-sphere, which has not time to form wave lines on its surface before it has passed into the drawn sheet or ever the revolving rollers. Furthermore, the rollers serve to bring a supply of fresh and uniformly heated molten glass into the area lying between the rollers and the sheet. The glass which is skimmed from the surface by the rollers and carried over them is subjected to the superheating action in the chambers $B\,B_{\gamma}$, as already explained, and is melted down so as to free the rollers from the adhering film, and restore the film itself to a proper working condition. Simple as the expedient of the rollers may seem, it meant months of painstaking observation and experimenting before they were conceived.

Operated by three shifts of men, of eight hours each, three men to a shift (one man filling in the batch to the continuous glass-melting tank furnace, one man watching the operation of the sheet-drawing apparatus, and one man cutting off the glass into sheets and removing them as the sheet emerges from the end of the annealing leer) this machine will produce sheet glass continuously, month in and month out, twenty-four hours a day, stopping only for repairs. The glass leaves the machine at an approximate rate of from fourteen to twenty-eight inches a minute (depending upon whether thick or thin glass is being drawn), and uniform quality of glass is maintained regardless of the speed at which the glass is drawn. Glass much thicker than the heaviest double-strength window glass, well as the single-strength, can be produced with perfect ease, the quality being midway between the best hand-blown and plate glass. The surface presents a most beautiful fire polish.

After the sheet has been formed it passes from a vertical to a horizontal travel over an idler or bending recler into an annealing leer, which bending roller receives the power necessary to start and keep it in motion from frictional power mechanism acting in conjunction with the frictional contact of the traveling sheet of glass. This combined application of power to the bending roller prevents it from marking or scratching the finished sheet. The glass is rendered sufficiently flexible at the bending point by a series of gas as illustrated in Fig. 7.

The Rumored Wireless Merger.

John W. Griggs, president of the Marconi Wireless Telegraph Company of America, denies published re-ports of the entrance of the Marconi companies into a merger of English and American wireless telegraph

A 31/2-inch rock drill, at full work, has been found to require 28 to 32 indicated herse-power at the cor pressor, but the actual power used against the rock was determined in a certain case to be only 1.7 horsepower. On the basis of 28 horse-power at the com-pressor, consequently, the efficiency of power at the drill bit was only 6 per cent.

PRESENT CONDITIONS AT PANAMA

President Roosevelt could not have cho opportune time for his recent visit of inspection to the Panama Canal; for that great enterprise has now been carried forward to the point at which the country is at last prepared to launch itself actively upon the work of construction. Hitherto, as we have shown in our editorial columns, the work has been almost entirely that of preparation. As far as the engineering staff was concerned, such excavation as has been done has been mainly of a tentative and experimental character, and directed, first, to the ascertaining of the actual value for future construction of the plant which was purchased from the French company, with a view to determining what must be sent to scrap and what could be used to advantage; and secondly, with a view to determining the unit cost of construction and the best forms of excavating machinery to be installed. The cost of excavation is greatly affected by the weather conditions, being of course higher in the rainy season than in the dry. It is found generally to vary in the Culebra cut from 50 to 75 cents per cubic yard.

ORGANIZATION: Under a recent executive order, the plan of administration has been simplified so as to concentrate the executive staff upon the listhmus and render its work more simple and direct. The listhmian Canal Commission will hold quarterly sessions on the Isthmus of Panama during the first week of February, May, August, and November of each year, and under the supervision of the Secretary of War, and subject to the approval of the President, it is charged with the general duty of the adoption of plans for the work of construction; the purchase of supplies; the employment of officers and laborers; the operation of the Panama railroad and the steamship lines; the govern-ment and sanitation of the canal zone; the making of all contracts for construction; and with all other mat-ters necessary for the construction of the canal as provided for by the Act of June 28, 1902. The old Executive Committee is abolished, and in order to promote harmony and secure results by the most direct methods, a new organization has been created, consisting of a chairman and seven heads of departments. The chairman, to whom supreme authority is thus given, is T. P. Shonts; and under him are seven departments. The First Department will be presided over by the Chief Engineer, who will have absolute charge of all engineering and construction work; the operations of the Personal Construction work; the operation of the Panama railroad as far as it affects canal construction; and the custody of all supplies and plant. In the absence of the Chairman from the Isthmus, the Chief Engineer will act for him in all matters requiring prompt attention. The Second Department, pre-sided over by General Counsel Richard Reed Regers will be concerned with the administration of civil government within the canal zone, and he will exercise through a local administrator the authority heretofore vested in the Governor of the Canal Zone. The Third Department, presided over by the Chief Sanitary Officer, Gen. Gorgas, will be concerned with all matters of sanitation within the canal zone, in the cities of Panama and Colon, and in the terminal harborn. The Fourth Department, presided over by the General Purchasing Officer, will be concerned with the purchase and delivery of all supplies, machinery, and necessary plant. In the Fifth Department, the General Auditor plant. In the Fifth Department, the General Auditor will have charge of general bookkeeping, property accounts, statistics, etc., and the audit of the government of the canal zone. In the Sixth Department, the Disbursing Officer will have charge of timekeeping and the preparation of payrolls and vouchers; and lastly the Manager of Labor and Quarters will have charge of the employment of all necessary labor; of the general personal record of all employees; of all quarters recorded to the same and of the presenter of comparison. provided for the same; and of the operation of sary hotels and mess houses.

Thus we find that the government has at length adopted what is practically the carefully elaborated and long-tested system used by our great railroad corporations in carrying out important works of construc

THE CONTRACT: Originally it was the intention of the Commission to build the canal with its own organization and labor. But because of the present unpre-ecdented and greatly extended industrial activity, and the consequent violent competition for all classes of superintendents, foremen, sub-contractors, skilled me-chanics, and even ordinary laborers, it became appa-rent that it would take the Commission several years to secure men and build up organizations for construction, which would equal in efficiency those which are now controlled by the leading contractors of the United States. The Commission came to the conclusion that by gathering together a trained corps of its own engi-neers and administrators of the highest experience and efficiency, and then calling in one or more of the largest contracting firms to do the actual work of construction under their guidance, it would be possible to complete the canal in shorter time and for less money than by day labor. Of the different forms of cantract considered, it was decided that the best proposition would be to let the actual work of construction to an association of contractors, each of which was an expert in some one or other of the branches of the work, on what is known as the percentage basis. The invitation for proposals based on this plan are now being considered by a large number of firms, and will shortly be opened by the government. Under this arrangement the contractor who receives the award will be paid an agreed percentage upon the estimated reasonable cost of the actual construction work as fixed by an engineering committee of whom the contractor will name two and the Commission three. This committee will estimate a reasonable time for completion of the canal, and a system of premiums and penalty, according as the

contractor does the work within or beyond such estimated time or cost.

any association contractors having an available capital of \$5,000, may sub mit proposals, and the bids must be accom panied by check or depos It of \$200,000 The successful must provide a bond for the faithful erformance o the work. If contractor fails to com plete the work within the time specified. will forfeit, for month's delay, \$100,000. If the work is completed in than specified time.

he will be paid a premium of \$100,000 for each month's time that is saved. The contractor must commence work within sixty days from the signing of the contract. He must perform the work in a manner that meets with the approval of the Chief Engineer of the Commission, and he must carry on the construction work, if required, during the night as well as the day is such shifts as the Chief Engineer shall direct.

One of the Fine Roads Being Constructed by the Canal

Construction Plant: During the past year the engineers have been making use, as far as practicable, of the French machinery, with a view to determining how much of it can be used in future operations. Incidentelly, experiments with this plant have served as an excellent guide in determining what character of new machinery it would be best to purchase. The vast amount of machinery shipped to the Isthmus by the French included 240 small Belgian locomotives which, after standing unused for twenty years, were, strange to say, found to be in first-class condition. The French had coated the interior of the boilers with oil, and the bright parts with white lead and tallow. Some of these engines, whose tractive power was only from

11,000 to 12,000 pounds, were put in use until more modern locomotives could be brought from the United States. The new locomotives of the American type, of which about 150 were ordered, have cylinders 19 x 24 or 20 x 26 inches. They are used in hauling dirt trains and serving the steam shovels, in the various cuts. The Commission also found about 3,000 French and Belgian dump cars of the small capacity of 5 to 8 cubic yards. These were put in service, but are too small adequately to serve the modern steam shovels.

The French methods of excavation consisted of side excavations with buckets, swinging derricks, of which about 250 were found by the Commission, and cableway



The Flat Arch Carrying Floor and Several Hundred Years
Old Proves That Earthquakes Are Not Severe.

outfits. All of these methods were found to be too slow and expensive to be suitable for up-to-date contractors' methods; this conclusion having been reached after a thorough test of the French machinery, as mentioned above. As the result of the experience gained, the engineers decided that the best method of excavation would be to use powerful American steam shovels with dippers of from 3 to 5 yards capacity, and a large number of these are now doing good work.

The small French dump cars have been replaced by specially-designed cars built in the United States. These cars are 40 feet in length. Already over 1,000 of them have been delivered at the Isthmus. Special side-unloading plows with unloading engines capable of giving a cable pull of 60 tons have been provided, and this plant is proving very efficient.

A large amount of the French machinery found at the Isthmus has been made use of for different classes of work from that for which it was designed. Thus, dredging engines have been erected as stationary shop engines, and excavating cableway engines installed for handling coal cars and coal chutes. Large stocks of rolled steel, steel plate, etc., have been utilized in the construction of shop roofs, reservoirs, and tanks for various purposes; while a number of Scotch boilers have found their way into boiler plants to supply steam for various shop purposes. Another important work has been the construction of a system for the supply of compressed air for drilling in the various large cuts on the canal. For this purpose three large compressor plants are under construction, which together will have a capacity of 30,000 cubic feet of air per minute. The air will be carried by a main pipe 10 inches in diameter, which will extend for the whole distance of 12 miles through the Culebra cut, and at 1,500-foot inter-

vals there will be 10-inch valves for supplying the air to adjoining localities.

calities. Although the French ma chinery found at a distance of four or five miles from the coast was in an excellent state of preservation as far as the metal work was concerned the floating dredges, scows etc., lying near the sea were so badly decayed and rusted that they fit for nothing but scrap, and one of our illustrations shows some of the costly machinery as it stands or floats to-day.

LABOR: At the opening of construction

the Commission had to depend upon such mechanics as had been gathered up from the French forces and from Central and South America. During the past twelve months, however, it has been possible to secure excellent grade of American mechanics who, or finding that the sanitary conditions are no worse and often better than can be found in our own Southern States, have gone to the Isthmus in satisfactory nur bers. The pay is naturally high, steam shovel engineers getting \$210, locomotive engineers \$125, drill runners \$180, and general foremen from \$200 to \$225 per month. All monthly employees are taken from New York to the Isthmus free of charge, and pay commences from the day the vessel leaves New York. When the men reach the Isthmus they find living quarters provided, consisting of a room with bed, mattress, and pillow, and board is furnished at the rate of about \$27 per month. Good men are encouraged to bring down their families, and at all points where skilled labor is employed, there is furnished reliable water supply and a good government commissary. An engineer writing in our esteemed contemporary, the Engi-



Photograppe by Underwood & Underwood





Abandoned French Dredges.

ns of

0F 70

nd

ce ve

in

d

d

ilof iait

st

m

m 01 neering Record, states that as regards the men's physical condition, there is no reason why one who is free from any kidney or liver trouble would not be as safe working on the Isthmus as almost anywhere in our own Southern States. He further states that the chief trouble from the climatic conditions is that the work is hindered by the occurrence of slides and the softening of the roadbed. The humidity of the atmosphere is entirely different from that of our interior States; while the temperature varies from 80 to 87 degrees in the shade. There is always a breeze when one is under cover, and a blanket is desirable on every night in the year.

THE GENERAL PLAN OF CONSTRUCTION: The bids which are shortly to be opened are made upon the plans for an 85-foot-level lock canal, of which we gave full description and illustration in the Scientific American of March 10 of this year. This is the canal recommended by the minority of the consulting board and adopted by the Canal Commissioners. The only important change that has been made is toward the Pacific end of the canal, where the location of one of

tion will be never less than 300 feet wide, and the total amount of excavation in this section is estimated at 24,000,000 cubic yards. Through the Culebra cut, a distance of 4.7 miles, the canal will marrow down to 200 feet, and out of this 39,000,000 cubic yards of clay, earth, hardpan, and volcanic material must be removed. At Pedro Miguel, 40 miles from deep water on the Atlantic, will be a single lock in duplicate, with a lift of 30 feet. This will call for over haif a million cubic yards of concrete and 10,000 tons of steel for the gates. Then will follow Lake Soza, 4½ miles in length, in which section the amount of excavation will be less than 2,000,000 yards. The Soza locks will be in a flight of two with a lift of 27½ feet each. These works will call for nearly 1,000,000 yards of concrete and over 18,000 tons of steel for the gates. The formation of this lake will call for the construction of three dams containing about 12,000,000 cubic yards of material.

The Panama section, reaching from Soza locks to deep water in Panama Bay, a distance of four miles, consists of a channel 50 feet deep below mean tide and 500 feet in width. The mean rise and fall of the tide

submarine lamp is described. It will hardly seem necessary to direct the attention of anyone to the desirability of pure water, yet in an article on water for table use some very common errors are exposed. Dr. Alfred Gradenwitz writes on a new stenographic machine. Prof. Edward C. Pickering discusses the need of an international southern telescope. Mr. Craig S. Thoms's interesting paper on "How Seeds are Carried" is continued. Mr. Walter J. May gives some hints on melting metals and alloys,

Automebile Notes

The Berlin Automobile Show was inaugurated on the 1st of November in the presence of a large crowd. It is held in the Exposition Palace of the Zoological Gardens. Besides two main halls for the cars, there is a third for motor boats and heavy-weight cars. Owing to an indisposition, the Emperor, who was to have presided, could not appear, but he was represented by the Crown Prince on this occasion, accompanied by Prince Henry of Prussia. The handsomely decorated stands show the most recent cars of German, French, Italian, English, and other makes. On the 6th the Emperor made a visit to the show. One of the features is the number of automobile cabs for public use which are exhibited. This is one of the questions of the day in Germany, and the new cabs are meeting with favor. Numbers of them are running in Berlin, and Hamburg is commencing to use them. The show promises to be a great success. It is organized by the Imperial Automobile Club of Germany, of which the Duke of Ratibor is president.

At the Dourdan races held in France the world's record for the kilometer (0.62 mile) was lowered to 20 seconds by Guiness upon a Darracq racer. The record was held for a long time at 21 3-5 seconds by Baras on a Darracq car and was then lowered by Hemery on the same make of car to 20 3-5 seconds in December, 1905. It thus took over ten months to beat it by 3-5 second, and the victory still falls to the Darracq racer. In the Dourdan race a 200 horse-power car of this type was entered, and Guiness piloted it. This is a formid-



Dam at Camancho for Drinking Water Supply.

the dams at the Pacific end of Lake Soza has been changed, the new site lying about half a mile nearer to the axis of the canal than formerly. The statement of the plan of construction of the canal, drawn up for the general information of bidders, arranges the work under fourteen sections. First is the Colon section, from the Caribbean Sea to the mouth of the Mindi River, which consists of a channel 42 feet deep at mean tide and 500 feet in width. It is not intended at the present time to construct the breakwater and jetty for the protection of this channel. Here it will be necessary to dredge out 8,455,000 cubic yards, mostly of soft mud, part or all of which may be deposited in the Gatun dam. Then follows the section from the mouth of the Mindi River to the Gatun locks, which will be 42 feet deep and 500 feet wide, and will involve 11,000, 000 cubic yards of excavation. The Gatun locks are to be in duplicate, two sets side by side. It is not yet decided whether to build a flight of three locks of 281-3 feet lift each, or a flight of two locks of 421/2 t lift. The size of the locks may be increased to by 1,000 feet; but on the present design of locks feet lift. 95 x 900 feet, the amount of excavation will be 3,660,000 cubic yards, and of concrete 1,302,780 cubic yards, while the steel gates will call for about 15,000 tons of Each leaf of these gates will measure not less than 50 feet in width and 75 feet in height. Truly gigantic proportions.

Adjoining the locks will be the Gatun dam, which it is proposed to build by sluicing material from the excavated canal prism. The dam will be 7,700 feet in length, 135 feet in height, and will measure 2,625 feet wide at its base. In this dam alone there will be 21,200,000 yards of material. In the center of the dam will be the regulating works for controlling the height of the water. The lake thus formed will have an area of 110 square miles, and for a distance of 15½ miles the channel will be at least 1,000 feet wide, with a minimum depth of 45 feet, which depth of water will be obtained throughout the whole surface level of the lake extending for 32 miles through the Culebra cut to Pedro Miguel locks. The channel in the lake sec-



Photographs by Underwood & Underwood

View Near Culebra Cut, Showing Character of Quarters Furnished Employees by the Commission.

PRESENT CONDITIONS AT PANAMA.

is 15 feet, but it may reach 22 or 23 feet. Finally, the Panama railroad will have to be relocated throughout almost the entire distance from the mouth of the Mindi River to Panama.

The Current Supplement.

The Ader "Avion," a beating wing flying machine, forms the subject of the opening article of the current Supplement, No. 1613. James Alexander Smith's treatise, "The Air in Relation to the Surface Condensation of Low Pressure Steam," is continued. Dr. H. W. Wiley writes on industrial alcohol, and gives some of its uses. Among the novelties described are alcohol stoves, lamps, coffee roasters, flatirons, heaters, motors, and the like. Furthermore, he dwells upon the use of denatured alcohol and the manufacture of coal-tar dyes, smokeless powder, ether, medicines, artificial silk, artificial vinegar, flavoring extracts, and wine. Dr. J. W. Martin publishes some remarks on the manufacture of mait. The use of tar on roads is discussed by Mr. James Owen. A novel

able-looking racer and has mounted on it an 3-cylinder motor with the cylinders placed at an angle. First it started off for the mile dash, and covered the mile in 47 2-5 seconds, as registered by the Mors electric chronometer, which we have already described. On resetting the device for the kilometer distance, the Darracq racer made a fresh start, after a number of others who did not make over 26 3-5 seconds, and succeeded in covering the distance in 20 seconds exactly, which is a fine performance and lowers the world's record.

As the result of continued rainstorms, the Trans-Baikal Railway has been washed away and damaged at several points; while the railway running round the southern end of Lake Baikal has suffered very much from great landslips between the stations of Baikal and Slyudyanka. Two trains have been overwhelmed by these landslips; two soldlers were killed, several of them were injured, and many of the cars were wrecked.

BEAUTIFYING THE ROADBED BY SODDING.

What an ideal roadbed should be, both for wearing qualities and appearance, is shown in four stretches of the main line of the Pennsylvania Railroad between Philadelphia and Pittsburg. Grassy banks sloping smoothly down, when the tracks are in a cut, are the features that strike the passenger's eye. It might be supposed that these sodded slopes are put there solely to please the eye, to make the Pennsylvania a good road to look at as well as to ride upon. This is a mistake—the grass is more useful than ornamental, and eventually it will mean the saving of thousands of dellars now spent on "maintenance of way."

sands of dollars now spent on "maintenance of way."

"Water," said a prominent railroad official in a recent lecture, "is the greatest enemy of the roadbed."

Water flowing down unsodded slopes causes erosion, washing dirt and stones into the ditch beside the track, and choking drainage. Perfect drainage is one secret of success in the maintenance of roadbed.

It was in the summer of 1905 that President Cas

the present improvement. order to reduce cost of maintenance as well as to make travel for the patrons of the Pennsylvania fortable, and altogether more agreeable. He appointed a committee of engineers of the company to prepare plans for a roadbed with draining facilities as near perfect as possible and the fifteen roadbed is the result of committee's re port. One of the two five-mile roadbed is near Philadelphia division, and the other near New

middle division. The two shorter stretches, two and a half miles each, are on the Pittsburg division, one near Cresson on the western slope of the mountain, and the other about fifty miles east of Pittsburg, at Hillside.

The Pennsylvania requires a ditch, ten and a half feet wide, on each side of a four-track road, and the bottom of the ditch must be three and a half feet below the level of the top of the tie. That means that there must be a decided slope from the lowest part of the roadbed to the ditch, so that water settling through the ballast will flow off rapidly.

The ditch itself is of ordinary soil, but the company has tried the experiment, in some places, of sprinkling it with oil to keep down both weeds and dust. Whatever method is adopted, the important object is to keep the ditch clean and unobstructed. It has been found that the sodded banks assist greatly in this. When it rains, the water pours down over them without bringing anything with it, and follows the ditch to the nearest outlet.

The cost of the improvement of even the fifteen miles has been very high. Seventy-three thousand cubic yards of new ballast were used in that short distance. This ballast was not to make the track more steady—the supply already there was sufficient for that—but to make the drainage perfect. The cost of sodding with blue grass was an even greater item. It was calculated by the engineers that sixty per cent of the entire cost was for cutting down and sodding the

The money will all come back, though, in saving of maintenance expenses. At present, work trains, crowded with laborers, have to be on the move all the time, for clearing ditches and putting in new ballast where it is necessary. In addition to the great cost of labor, the interference with traffic is a most important consideration in this constant overhauling.

Antimony has a hardening effect when added to lead: a small quantity of bismuth gives the alloy the property of expanding at the instant at which it solidifies, the result being a perfect cast from the mold.

Engines Drivon by Blast-Furnace Gas.

In order to show the great benefit which is obtained operating low-carbon gas engines directly from blast-furnace gases we may cite some of the recent figures which have been taken from experiments made Continent, where many such motors are in use in blast furnaces for operating rolling mills and other machinery. In the blast furnace, the production of gas available for the engines is stated to be 2,700 cubic yards per ton of pig iron produced, making the necessary deductions for losses and for the quantity of gas needed for the reheating. The gas gives from 800 to 1,000 calories per cubic yard. This quantity of gas utilized in a steam engine, by burning it under the boilers, would give only an amount of energy available represented by 260 horse-power-hours, while in the case of motors which use the explosive force of the same amount of gas we find that the energy is three times the above amount. This is greatly in favor of the use of such engines, especially as they





BEAUTIFYING RAILROAD ROADBEDS AND PROTECTING SLOPES BY SODDING.

are now very reliable in their action and are built in large sizes. As the blast-furnace gas does not contain any products of distillation, but only a quantity of water vapor and dust which are easy to separate, the engines do not need to be cleaned as often as ordinary gas engines. With a good set of scrubbers for the gas, a motor can be operated several months at a time without needing to be cleaned. Seeing that the blast-furnace gas does not contain hydrogen, there is no danger of a premature explosion of the gas in the motor, even when working at a very high compres-

The native mass copper of Lake Superior has the highest electric conductivity of any known copper. A sample cut from the most compact portion of a mass, rolled and drawn into a wire of 0.104 inch diameter and annealed, gave a conductivity of 102.5 Manha sson standard. Cathode copper, carefully deposited with a low current, and prepared in the same way, gave just as high a conductivity.

THE ANCESTORS OF THE ELEPHANT.

The ancestors of the elephants of the present day have become well known to palæontologists through the fossilized remains, and even frozen carcass which have been found practically all over the world. The two living species of elephant are the last survivors of a group generally known as mammoths or mastodons, which formerly spread over all the great continents and inhabited temperate and Arctic as well as tropical regions. Various species of these elephants or mammoths have been found in every country of Europe, in Asia and Africa, and in the western hemisphere from Alaska to Argentina. The remains of these giant creatures are so abundant in Siberia, that fossil ivory forms a fairly large article of commerce, The mastodons, distinguished from the true elephants principally by a less complete specialization of the grinding teeth, had an almost equally extensive range but inhabited more especially the temperate regions during the Pliocene and Pleistocene epochs. Primitive

mastodons lived in Europe and North America during the Miocene epoch. They were of smaller size than the later mastodons, and had small tusks in both upper and lower jaws. In some of the older species the upper tusks curved downward, and the lower ones upward, in a manner that indicates their origin from chisel-shaped incisors, like those of rodents. From this stage up to the present elephant a complete evolutionary series can be traced, but the earlier stages in the development of the Proboscidea are not known, though they are probably Asiatic. Mammoths have been found in the Arctic regions imbedded in masses of ice, which so preserved them that the flesh could be used as food for sledge dogs and even human beings. This preservation has enabled us to become familiar with the mammoth in every particular, even to the food upon which it lived, for quantities of this have, in certain instances, been, found between the animal's jaws, or partially digested, in the s'__ch.

Although the elephant can be considered an

ungulate, nevertheless he presents such remarkable differences in the structure of the skull, that naturalists have given him an isolated posi-tion in the animal kingdom.
The skull includes many prominent bones, and numerous internal pass separated b y partitions. The nasal bones are short, and the nostrils form upwardlyleading duct.
Compared with the size of the skull, the brain, although the largest found among the mammals, is ex ceedingly small and has strongdeveloped convolutions. in the rodents, the teeth are composed of in-

cisors and molars only. The modern elephants belong to the specially-created sub-class Proboscidea, which comprises only two varieties, and the elephant, therefore, stands alone in the animal world, a paradox in the natural systems based upon consanguinity or upon

The first traces of pachyderms in any way related to the elephant are found in the Miocene period. In those days the climate of the temperate zone was subtropic, and together with the tapir, still found in Central and South America and in southern India, the dinotherium roamed the luxuriant forests of his habitat. Plece by piece the bones of this proboscidean have all been gathered, and show that he was an animal some 14 feet in height, with a trunk and long column-like legs. Most peculiar is the formation of the lower jaw, the forward portion of which is considerably elongated. This strongly-developed symphysis bends downward at right angles, and carries a pair of strong incisors turned backward, describing a curve not unlike that of the tusks in the upper jaw of

the walrus. These tusks show in cross section a dense, concentric, radiating mass of ivory, the outer surface of which is sometimes circular and sometimes oval. The lower jaw of the dinotherium is unique among all mammalian jaws, and constitutes an especial differentiation of species. The resemblance between the molars of the dinotherium and the tapir is very strong, and from this resemblance Cuvier was led to conclude that the first discovered remains of a dinotherium were those of a tapir. The species is found in the middle Miocene strata of central and southern Europe and in the upper Miocene to the lower Pliocene in the same regions, as well as in the upper Miocene of south-

ern Asia. In the mastodon the formation of the head was more elephantlike, while the body was onger and heavier than that of the elephant, with thicker bones. The cervical vertebræ were not so short, and consequently the neck was longer and more mobile. During the middle Miocene, mastodons inhabited central and uthern Europe and north Africa, and during the upper Miocene southern and eastern Asia as well. The abitat remained the same entire Pliocene for the period, with which they disappeared, the cause of the disappearance being unknown, although it has being been conjectured that man had a hand in the destruc-tion of the genus. In America the

mains are first found in the upper Miocene, becoming more widely distributed in the lower Pliocene, and being found in the beginning of the upper Pliocene in South America. In both North and South America they are found even down to the Pleistocene period, but for some inexplicable cause they disappear with the first appearance of man. The geologically older forms of the genus Mastodon ess, besides a pair of huge auxiliary canines or s, a similar pair somewhat less markedly developed in the mandible. The mandible tusks are not downwardly disposed as in the jaw the dinotherium, but project forward with a slight upward curve. The mastodon molars resemble those of such suilline animals as the hippopotamus, but in the later forms the structure of the molar more closely approaches that of the elephant grinder until a complete transitional form is developed, occurring with a simultaneous retrogression of the symphysis together with the disappearance of the mandible tusks. mastodons had a more compact dental enamel than any of the other mammals and were, on that account, good

masticators, the food of the genus undoubtedly consisting of plants, reeds, and twigs of trees.

A The later upper Pliocene mastodon when mature no longer had mandible tusks, the alveoli, or sockets, soon growing together after the milk tusks had disappeared. The molars in this species are characterized by alternating cusps in each half ridge. The Ohio species, called by the Indians "Father of Oxen," is better known and is generally recognized as typical. Of this species the most complete skeletons have been obtained from the banks of the Hudson, but large quantities of bones have been found in the salty bog soil of Big Bone Lick, Kentucky. The bones are very



Mastedon Bones Found in American Gulch.

massive and the vertebre long, while the upper tusks have a decided upward curve.

A transitional form between the later mastodon and the elephant is found in the stegodon. In this genus the lower incisors are lacking and the upper are enormously developed, while the molars consist of from six to twelve low convex transverse ridges, the depressions between which are usually filled with cement. The genus has four species, and it flourished from the Pliocene to the Pleistocene in southern India and eastern Asia.

The elephant evidently at some time migrated from his primeval southern Asiatic home. At the present time the last species inhabit southern Asia and the tropical regions of Africa, whither they migrated at a comparatively late period.

The list of vessels which have been engined in England with Parsons' turbines to date represents a total horse-power actually completed of about 280,999.

The Temperature at Which Water Process in Scaled Tubes,

Prof. H. A. Miers, F. R. S., of Oxford, and Miss F. Isaac presented an important communication on "The Temperature at Which Water Freezes in Sealed Tubea," before the recent meeting of the British Association. The authors had shown in 1905 that in a cooling supersaturated solution in which a few crystals were growing while the solution was being stirred, the refractive index rose to a maximum at a certain temperature and then fell suddenly; at that moment profuse crystallization took place. As the same solution inclosed in a sealed tube, so as to be protected from

access of crystal germs, crystallized in a shower at exactly the same temperature, this seemed to be the temperature of spontaneou tion. Crystallization at a lower temperature could be produced only by inoculation of the solute the nitrate. chlorate. chloride, sulphate of sodium, various alume, etc.or of an isomorphous stance. The present sixty eight experiments.

Miers stated, had Prof. been made with water inclosed in sealed tubes which in sealed continuously violently shaken in a bath of brine, cooled by of a refrigerating coil, and by a wooden of horse-shoe stirred plunger shape perforated with holes. The initial brine

temperature ranged from + 9 deg. to -2 deg. C., and the rate of fall was about 2 deg. per hour. The tubes were of ordinary or Jena glass; some were newly made up, others had been used for weeks; the water was tap water, or distilled water, or pure water of conductivity 1.1 × 10°; the tubes were about half full, and the experiments lasted from seventy to five minutes each. All the tubes frose at temperatures between -2 deg. and -1.6 deg. C., the mean for all the experiments being -1.86 deg. C., and for the pure water -1.9 deg. C. The ice generally made its appearance at the bottom of the tube, and grew at first rapidly in fan-like crystais, and then in a cloudy shower. The authors concluded that -1.9 deg. C. was the temperature at which pure water froze spontaneously in the absence of solid germs of ice, and it was remarkable that, according to Pulfrich, this was also the temperature at which supercooled water possessed a maximum refractive index. The effect of friction had been studied by introducing glass, garnet, or lead into the tubes; the water then froze at -0.4 deg. C.



Mastedon Head Unearthed at a Depth of Forty-two Feet-Length, 4 feet; width, 2 feet 4 inches; tusks, 7 feet 6 inches.



Mastedon Skull and Tusk Found in Quartz Creek, Yukon Territory.




A NOVEL TWO-PART HOOK.

The ordinary hook, used by lumbermen for attaching a cable to a log, is quite liable to become unhooked whenever the cable is slackened. To prevent such annoying occurrences, Mr. Elias Carlson, of Ka-Cowlitz County, Wash., has invented a two-part hook so designed that it cannot accidentally be unhooked. As shown in the accompanying engraving, the improved device consists of two overlapping hook nbers mounted to swing upon a bolt to which the usual shackle is secured. Contrary to the common practice, the hook members swing laterally toward each other, that is, the axis is parallel to the general planes of the hook members instead of being at right angles thereto, as in previous two-part hooks. The overlapping portions of the hook members are flat-tened at their adjacent sides, so that when they are swung to closed position the ends will offer no projecting obstruction to the free movement of a cable within the closed hook. In this position the mem-bers form a practically continuous closed ring. In order to keep the members in closed position they are attached to a spring, which is coiled on the bolt In a recess between the members. The extent to which the hooks may be opened is limited by a pin on one member, which engages a slot in the other. One of the principal advantages of the invention is that the hook is free from any projecting parts, which are liable to catch on brush, or the like, in logging Another important feature of the invenoperations. tion is that the ends of the shackle are on the outside of the hook, and thus do not interfere with the cable.

*** AN IMPROVED TIE-BAR.


very simple design has recently been invented by Mr. J. F. McKechnie, of Eleele, Kauai, Hawaii Territory. The device is particularly adapted for connecting the rails of a railway track at curves to prevent the rails from spreading. It may also be used to advantage on such portions of the track as run over soft ground, or at other dangerous spots; for the rails are tied to gage, and cannot be displaced. Furthermore, the tie-bar relieves the ties of undue The chief merits of the improved tie-bar lie in its simplicity of construction; the facility with which it may be attached to the rails, and its absolute fixity when applied. A plan and a side view of the invention are shown in Figs. 1 and 2 of our engraving. It will be observed that the tie-bar comprises a tie-rod with hooked ends, which engage brack-ets secured to the opposite rails, the members being locked in place by a key driven between one end of the tie-rod and a hook on the adjacent bracket. This bracket is shown in detail in Fig. 3, and it differs from the other bracket, Fig. 4, in having a longer base, which is hooked under at its inner end. Each bracket is formed with a longitudinal slot in the base, ad a groove leading from the slot to the inner end of the base. Each bracket is also formed at its outer end with an upright projection of such shape as to closely fit the outer face of the rail which rests on This projection is braced by a flange or The device can be applied to the rails in a web. few seconds. First the brackets are slipped under the opposite rails, then the booked ends of the tieinserted through the slots in the brackets, after which the key is driven in place between the d base of the bracket, Fig. 3, and the rod. will be noticed that this end of the rod is formed with adapted to bear against the base of the rail. Evidently the rod can easily be removed when deby driving out the key; but it is absolutely The groover fixed against accidental misplacement. ase fit closely against the rods, and prevent



the brackets from creeping along the track. We are informed that the invention has been put to a severe practical test on a railroad for four years, and has given entire satisfaction.

Evening Technical Courses at Columbia University,

The Board of Extension Teaching of Columbia University announces a series of nine evening technical courses which will be given at the university this winter, beginning December 3, and lasting twenty



A NOVEL TWO-PART HOOK.

veeks. The courses are under the immediate direc tion of Prof. Walter Rautenstrauch of the Faculty of Applied Science, and are to be given by professors and instructors of the university and other persons especially qualified. Moderate fees (\$7.50 to \$15) are charged, and most of the courses are for two evenings a week. The courses are as follows:

GINEERING PHYSICS: As illustrated in the mechanical plants of modern buildings. (1) An elementary study of physics; (2) a practical study of steam and electrical machinery, heating, ventilating, water system, wiring, elevators, etc., included in the plant Columbia University. For two classes of students: those wishing an introductory study of physics as preparation to advanced study in electricity, steam, tc., another winter; those desiring practical training for positions as superintendents of buildings, engirs, janitors, etc.

ELEMENTARY MATHEMATICS: Those parts of arithmetic, algebra, geometry, and trigonometry used in technical work. Practice with engineering handbooks,

DRAFTING: A beginner's course; fits for positions as draftsmen; reading of drawings, etc.

STRENGTH OF MATERIALS: A lecture course for those who design or manufacture machinery or modern structures. With this course should be taken either the first or second of the two following courses in design.

MACHINE DESIGN: Advanced drafting, computations and designing for persons engaged in the design and manufacture of machinery.

STRUCTURAL DESIGN: Advanced drafting, computa-tions, and designing for those who do structural work. ELECTRICAL ENGINEERING: A course especially for those engaged in electrical work of any sort.

STEAM ENGINEERING: A course for those engaged in the manufacture of management of steam machinery of any sort.

SPECIAL ENGINEERING PROBLEMS: A study of any special elementary or advanced engineering problems desired by the student. Individual instruction will be arranged for such a period of time as the special problem may demand.

The courses will be given in the buildings of Teachers' College, Columbia University, at West 120th Street and Broadway, which affords necessary lecture rooms, laboratories, drafting rooms, etc. A complete catalogue of these courses will be sent on request by addressing Evening Technical Courses, Extension Teaching, Columbia University. Personal information may he secured Tuesday and Thursday evenings, between 7:30 and 9 o'clock, from Mr. Benjamin R. Andrews, Room 111 Teachers' College.

At the Lick Observatory, says the American Ma-chinist, they have recently spectroscopically determin-ed the distance from us of the nearest fixed star, the result being stated as follows: Light, traveling with a speed of 186,000 miles per second, requires 41/4 years to reach us from that star. And we figure it out like this: Length of sidereal year, 365 days, 6 hours, 9 minutes, and 9.33 seconds, which is 31.558, 149.33 seconds, and four and a quarter years are therefore 134,122,134.625 seconds. The distance then (call it mean or magnificent, as you please) is 24,946,717,-045,365 miles.

Thirty-one New Variable Stars

The study of the distribution of variable stars by superposing a negative on a positive of a different date, has been continued this fall by Miss Henrietta S. Leavitt, of Harvard Observatory, with the follow-ing results: Five plates taken with the 24-inch Bruce bec. = +23.5 deg., and having exposures of from one to four hours, were examined with the usual care, and only one new variable was discovered. The plates, most of which are of excellent quality, cover a region five degrees square with good definition, and it is estimated that about 150,000 stars were exam-The Pleiades are near the center of the plates, ined. The single variable discovered is in remarkable contrast with the large numbers found in other regions by the same observer, and announced in recent circu-The only known variable in this region is 032723- Fauri, which is near the edge of the Apparently conditions in the vicinity of the Plejades favor unusual constancy in light, as no stars were even suspected of variability, though there are many suspected variables in the other regions as yet to be examined in this way.

A plate with the nebula of Orion in the center, R.A. = 5h. 30m., Dec. = -5.5 deg., exposure 74m., taken last winter, has been compared with an early plate, with the result that two new variables were found, while seventeen known variables were rediscovered. The method used is not adapted to the discovery of variables in regions where nebulosity in strong, unless the variations are large. The region of the Southern Cross and the "Coal-Sack" has been examined on thirteen plates, three of which have centers at about R.A. = 12h. 20m., Dec. = -62.5 deg., and ten have centers at about R.A. = 12h. 50m., Dec. = -62.5 deg. Twenty-eight new variables were discovered, and the known variables, 121861, R Crucis, and 131360, -Centauri, were also found.

POLLEN-COLLECTING DEVICE.

We illustrate in the accompanying engraving a simple device by means of which pollen may be collected from certain flowers or blossoms, for use in the manufacture of medicines and the like. In brief, the device consists of a vessel provided with means for holding the slips or twigs bearing blossoms from which the pollen is to be collected. The vessel is filled with water, which keeps the twigs fresh and ripens the blossoms. The latter overhang the edge of the vessel, so that the pollen falls on to a paper on which the vessel is set, and may be easily collected from time to time. As will be observed, the device is the ex-treme of simplicity. A rectangular tank is used, which is preferably made of sheet metal. Over the top of the tank is a sheet-metal plate supported upon two longitudinal and two transverse rods, the edges of the plate being bent around the rods. This cover plate is of smaller area than the top of the tank, so that a narrow channel or opening is formed around the entire perimeter of the plate. The rods project across this opening, their ends being bent over the rim of the tank. Into the openings around the plate the twigs and branches are inserted, their lower ends being immersed in water. The branches are tilted so that their upper ends project beyond the sides of the To keep them in this position and prevent them from sliding too far into the tank, the cover plate is cut at the center to form a pair of flaps, which are bent downward, as shown, and engage the stems. As stated above, the tank is placed upon a sheet of paper, on which the pollen falls as the blossoms ripen. desired, the water in the tank may be drawn off, without disturbing the branches, through a tube connected to a stop-cock near the bottom of the tank, and fresh water can be poured through the opening in the cover Handles are provided for the removal of the tank when the pollen is to be collected from the paper. Mr. Eugêne Moulié, of Jacksonville, Fla., has just se cured a patent on this pollen-collecting device.



POLLEN-COLLECTING DEVICE.

ld

is

rly

lis lig-

ave

cis.

im ted

de-oldich

the

the ex-

the dges

c, so ound

oject plate

ed 80 f the them

are As

with-ected

fresh cover f the paper.

st 80

RECENTLY PATENTED INVENTIONS.

ELECTRIC GAS-LIGHTER.—G. Giorgi, Fiorence, Italy. This invention has for its object the opening and closing of gas-taps and the lighting and extinguishing of the gas by the means of an electric current; and it comprises an electromagnetic gas-tap, an automatic electrochemical lighter, and an arrangement of cut-out in the electric current.

POTATO-PLOW.—J. M. DRAKE, Shawano, Wis. In this case the invention has reference to improvements in potato-plows, the object being the provision of a device of this character that will be simple in construction, inexpensive, and having a novel means for shaking pensive, and having a nov the dirt from the potatoes.

the dirt from the potatoes.

SUBSOIL-PLOW.—E. BIPPART, Arnstadt,
Thuringia, Germany. This invention relates
to improvements in subsoil-plows whereby
they are enabled to better and more easily cut
through or to push aside roots in the soil.
The improved subsoil-plows will also be able
to work properly in a bouldery soil or in a
soil full of stones.

MACHINE FOR WORKING THE SOIL-MACHINE FOR WORKING THE SOIL.—
L. F. BASEETT, Redding, Cal. One purpose of
the present invention is to provide a machine
adapted to be drawn over a field and operated
automatically to break lumps upon lumpy,
cloddy lands or where more than the usual
fineness of soil is desired after it has been
plowed and perhaps partially harrowed down.
SEEDING DEVICE.—J. M. OPPER, Gresham,
Neb. In many devices used for selecting and
dropping corn into a hill the seed-plate is
operated by means of a clutch, which is thrown
into and out of engagement with its adjacent

operated by means or a circum, which is individual into and out of engagement with its adjacent members to start and stop the plate between bills. This constant action of the clutch is a source of great inconvenience and trouble at times and one of the objects of Mr. Opper is to dispense entirely with the use of the

clutch.
COTTON-PICKER.—R. W. Ivy, New London,
N. C. In the present invention toothed belts
are caused to reciprocate instead of constantly
traveling in one direction, they being suitably
connected with a toothed frame which is
reciprocated by mechanism actuated from a
power-driven shaft located upon the wagon
frame. It is more particularly an improvement upon that forming the subject of Mr.
Ivy's former patent.

Of General Interest.

UMBREILA.—G. A. MANGELSDORF, Houston, Taxas. The top of the umbrella may be tilted at any inclination to the body portion of the stick. The supporting stick may also be lengthened by sliding the inner section in or out of the outer. When the upper end of the umbrella is set at an incline to the main portion of the stick, the handle may be rotated to bring it into grasping position without changing the position of the inclined portion. An extensible handle enables the umbrella to be packed for traveling. The same construction may be made use of in a parasol with equal facility.

COPY-HOLDER.—E. Dr. F. Holz, Morris-

equal facility.

COPY-HOLDER,—E. DE F. HOLT, Morristown, N. J. The holder consists of rollers journaled in standards between which the copy is passed and carries at one end a coverplate to obscure the writing on the pad or copy-book. One of these rollers is adapted to be interchanged and an attachment brought into operation which will hold the copy stationary and permit the work to move between the rollers in the opposite direction from which the copy did in the first instance.

BURNER FOR COAL-TAR.—T. COUGHLAM, New York, N. Y. The burner is especially adapted to be constructed of piping, and will operate efficiently. It may be readily cleaned and the mouth is so formed as to produce a flame of desirable form. The invention pertains to burners for liquid or sensitized fuels, such as hydrocarbon, and is intended especially for burning coal-tar.

CONTROLLING DEVICE FOR DOUBLE

CONTROLLING DEVICE FOR DOUBLE DOORS.—W. B. REIS, New York, N. Y. In this instance the device is adapted for use particularly in connection with doors of music-cabinets or the like, the object being to provide a simple means whereby companion doors may be swung simultaneously to open position or closed position by the manual manipulation of one door.

one door.

BAROMETER.—W. C. PLANK, Las Flores, Mexico. The range of an ordinary mercurial barometer at a fixed level is very small, usually not over two inches. By the use of the inventor's principles his instrument can he made in various forms and conveniently constructed in such a manner as to be readily carried in the pocket, and given a range twice as great as that of ordinary barometers.

DOUBLE CHARCHETER A. L. CORRE

as great as that of ordinary barometers.

DOUBLE CIGAR-CUTTER.—J. L. OBER-MATER, New York, N. Y. The cutter is carried in the pocket, the more particular object of the improvement being to provide the cutter with a large number of cutting edges so disposed as to enable different pairs of them to be used independently of other pairs, the arrangement being such that when the cutter is folded and ready to be carried in the pocket the cutting edges are harmless.

N. Y. The object of the invention is to produce a structure which may be folded into compact form when not in use or for transportation and which may be readily opened and set up when desired. It relates to horses or trestles such as are used by artisans and workmen for supporting scaffolds.

vorkmen for supporting scaffolds.

LADDER-ROUND.—S. J. LAMORA, Danville,
Vt. The round is capable of being quickly
attached and detached to or from wire or
hemp ropes, bars, chains, or the like whereby
a ladder may be built up in a short time and
disassembled to pack it in/ small compass.
This construction is especially desirable as a
life-saving means for the upper floors of buildings in constructing at short notice a ladder
for reaching the ground as in case of fire.

NON-REFILLABLE ROUTLE—A C. WAY

for reaching the ground as in case of fire.

NON-REFILLABLE BOTTLE.—A, C. WAY,
Perry Center, N. Y. The bottle is in that class
which are provided with one or more internal
stoppers having a movable valve for closing
an exit-passage. In operation a ball is in a
position that closes the lower passage of the
stopper against ingress of liquid; but upon
tilting the bottle so that the ball rolls forward to the upper end of the pocket, the
above named passage is opened, and liquid may
then flow around the ball through the angular
groove of the stopper and out through the top
groove.

Hardware.

Hardware,
CROSSCUT-SAW.—F. W. McIntosh, Montesano, Wash. The saw provides clearance in the kerf for the saw-blade to pass easily through, to allow the cutting edges of the cutting-teeth tq strike the wood at a more scientific angle for cutting without danger of becoming "timber bound" or likelihood of the booth-points being broken off in resinous or knotty timber. There is neither necessity for undue physical exertion in the operation of sawing nor need of frequent filings to keep the saw in working order. working order

Heating and Lighting.

Heating and Lighting.

HEATING APPARATUS.—J. H. Koons, Anderson, Ind. The object of this inventor is to provide a heater in which air under high and low pressure with crude oil or gas are used as fuels that will be simple in construction and by means of which an intense heat may be maintained under a hot biast, a system particularly adapting the device for use in connection with meiting-furnaces, tempering or annealing furnaces, blacksmiths' forges, etc.

WATER-HEATING APPARATUS.—J. A.

WATER-HEATING APPARATUS. — J. A. Hosr, Jacksonville, Ill. The apparatus is more especially designed for heating a small quantity of water at a time, such as is required for bathing or other purposes. It is arranged to effectively heat the water in a very short time with an economical expenditure of fuel, such as gas, oil, or the like.

such as gas, oil, or the like.

AGITATING SULFUR-BURNER. — J. C. Wise, Watertown, N. Y. Among the general objects of the invention are: a comparatively large capacity for a given area occupied by the burner; the production of a richer and more uniform gas; perfect combustion of the sulfur known as "Louisiana" sulfur, a saving of labor, due to the movement of the sulfur into the pot being to some extent automatic; case of regulation of the admission of air, and, lastly, uniformity of admission of air into different parts of the burner.

HOT AIR GENERATOR.— C. I. ROWNE.

ferent parts of the burner.

HOT-AIR GENERATOR.—C. L. BOWNE,
Keyport, N. J. The apparatus is designed
primarily for use in drying brick, but may be
used especially for heating drying-rooms. It
will economically heat the air to any desired
temperature and force it through a duct or
tunnel to the place where it is to be used;
and it will be impossible for smoke and gas
coming from the furnaces to intermingle with
the air so heated.

Machines and Mechanical Devices,

Machines and Mechanical Devices,
FUEL FEEDER OR STOKER FOR FURNACES.—J. T. Jenkins and E. Trackwell,
Massilion, Ohio. This invention relates to improvements in puddling, scrap, and heating furnaces used in iron and steel mills and particularly to a stoker employed in connection therewith, the object being to provide a novestoker by means of which the coal will be
evenly distributed.

GRAIN SHELLING AND HULLING DE-VICE.—O. DE A. CAMARGO, Rio Claro, Brasil. In the present patent, the invention has reference more especially to devices for shelling and hulling coffee, although equally applicable to the shelling and hulling of the control of the shelling and hulling and shelling and she to the shelling and hulling of other grains or materials. The device is intended to be economic from a manufacturing standpoint, and is exceedingly simple in construction.

and is exceedingly simple in construction. KEYBOARD FOR MONOTYPE PERFORAT. ING-MACHINES.—A. J. Wansworth, Washington, D. C. This machine is designed to produce perforated record-strips or controllers which are subsequently used to govern other mechanism, such as type-making machinery of mail order novelties.

DOUBLE CIGAR-CUTTER.—J. L. OBER-AXER, New York, N. Y. The cutter is carried in the pocket, the more particular object of the production of printing-type. The invention is in the nature of a keyboard for monotype perforating-machines of the general character set forth in the patent formerly issued to 7. Lanston.

PUNCHING, STAMPING, AND LIKE MARMING, AND LIKE MARMING, AND LIKE MARMING, Wilking, and the like is provided with means whereby in the event of the tool meeting with selection making machiners.

FOLDING HORSE.—L. NOLAN, New York, Ne

resistance which it is unable to overcome such damage to the machine and its appurtenances as would otherwise result may be avoided. The devices used for the above purpose permit of their introduction into presses already in use or permit of their application to the usual styles of machines without calling for radical modification in their general expensions and proportions. e and proportions

TUMBLER - WASHER. -ROTARY TUMBLER - WASHER. — F. W. WILL, Aurora, Ore. The object of the invention is to provide a device which is adapted to rapidly and thoroughly cleanse both the inside and outside simultaneously of tumblers, glasses, mugs, bottles, etc. The mechanism will automatically adapt itself to the various sizes and shapes of the articles to be washed without any adjustment whatever.

without any adjustment whatever.

PAPER-GAGE.—W. SMITH, New York. N.

The machine designed for use with sheets
of paper of one size formed the subject-matter
of a patent formerly granted to Mr. Smith.
The present invention provides means whereby
machines can be operated in connection with
sheets of different sizes. For this purpose he
provides movable or adjustable paper-guides
on the plunger of the machine and locates
registering marks on the plunger, stenciladder, and stencil.

MOUNTLY MACHINE — I. MARTIN



HINTS TO CORRESPONDENT

nes and Address must accompany all letters or no attention will be paid therefo. This is for our information and not for publication, arances to former articles or answers should give date of paper and page or number of question, niries not answered is reasonable time should be repeated; correspondents will bear in wind that some answers require not a little recearch, and, though we endeavor to reply to all citizer by letter or in this department, each must take his turn.

letter or in this ueparamental trans.

It is turn, the transport of the tr

addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Boisnika American Supplements refurred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of nrice.

price.
Minerals sent for examination should be distinctly marked or labeled.

The present investion provides mean whereby a machines can be operated in connection with the state of the purpose believe to the polagor of the machine and locates registering marks on the plunger, stenctive production of the pullager of the machine and locates registering marks on the plunger, stenctive production of blocks at exceedingly low labor cost in the including the mode, as to person the production of blocks at exceedingly low labor cost and at the same time to make a block that the including the mode, as to person ordinarily endured to the cost of blocks at exceedingly low labor cost and at the same time to make a block that discovered the cost of blocks at exceedingly low labor cost and at the same time to make a block that discovered the cost of blocks are carefully lower and the same time to make a block that discovered the cost of the continuation of the cost of the cost of the cost of the production of the cost of the cost

(10235) F. W. L. asks: In order to generate a current in a closed coll of wire, is it necessary to after the number of lines of force passing through the coll, or can a current be generated by simply cutting equal number of lines with one part of the coll, with con-stant speed? A. To generate a current of choc. tricity in a coil of wire it is necessary to vary the number of lines of force passing through the coil. If the same number of lines are cut each second, there will be no current produced in the wire,

(10236) R. S. D. asks: I have a (10236) R. S. D. asks: I have a four-magnet telephone generator which rings through 50,000 ohms, which has been through a fire. Is there any way by which I can charge the magnets over again, and how much wire will I need to wind the armature? A. The Carty bridging bell, which is used for long-distance telephoning, is said to be wound to 1,000 ohms with No. 38 B. & S. wire. This would require nearly three-fourths of a pound of wire. If your magnets are not burned so as to injure the steel, they may be tempered and remagnetized. They will then be as good as they were before.


(10237) R. H. asks: I desire to make (10237) R. H. ABIE: 1 desire to a zheostat for use with an arc lamp in my stereopticon. Have you a description in any of your Supplements of such an appliance, with instructions how to make it? A. A very good form of rheostat is shown in Supplement 865, price ten cents. This may be very good form of rheostat is shown in Sup-trament 865, price ten cents. This may be sdapted for use on a lamp. The slate sides are not needed, but the frame should be of fron insulated by asbestos. A plate of slate should be used for the blocks and swinging arm to vary the resistance. The size of wire depends on the amperes the lamp carries. No. 12 German silver will probably be heavy enough. Bubtract forty-five from the voltage of your current and divide the remainder by the amperes the lamp takes. This gives the chims of resistance required in the rheostat, al-though it will be well to use about one-fifth more wire. You can sllow fifty feet of the wire named above the ohm.

(10238) E. K. E. asks: Would you (10238) E. K. E. asks: Would you be kind enough to tell me the exact length of German silver wire of a suitable size for a resistance of one ohm, the wire being such as is commonly sold by electric supply houses? A. The length of wire for one ohm depends upon its size. Supply houses keep all or nearly all sizes of German silver wire to correspond to those of copper wire. To find the number of feet in an ohm, divide the number of feet of copper wire in an ohm by 13. The quotient will be the number of feet of German silver wire in an ohm.


(10239) D. A. H. asks: Have scichilats generally accepted the theory that the electric current does not flow through a wire, but follows the space around it? A. An electric current flowing with unvarying intensity flows through the material of the wire, flows in the wire, and also sets up a magnetic flow around the wire. In this field a magnet is attracted by the lines of magnetic force. When an electric current flows with a varying intensity, either increasing or diminishing in intensity, either increasing or diminishing in intensity, as, for instance, starting with a sudden rush and as auddenly dying out, then electric waves are thrown off into the space around the wire, it may be with great force, so that they are sent many miles. It is these waves which are used in wireless telegraphy. They are not in the wire. The wire is but a core or center around which the waves whirl with tremendous energy. We are but beginning to learn their power and value, and have not yet harnessed them and broken them into our use and service. 2. Referring to the article entitled "Humidity and Heating Systems" in your Scientific American, why is it that the humidity of the air in the house and heated? A. The humidity spoken of is not the amount of moisture in the air, but the percentage of moisture as compared with the total amount of moisture which the air could hold at that temperature. Air saturated with moisture is said to have 100 per cent of humidity. The whole name is relative humidity, which expresses the meaning better. It is the moisture relatively to complete saturation. Now, the capacity of the air to hold moisture varies greatly with the temperature. In a summer morning fog may lie thick over the orith, because the air was saturated with moisture, and the excess of water appeared as fog. The sun chase, warms the air and the fog disappears. Why? Not because there is any less moisture in the air than earlier, for the dew and fog will come again at nightfall and last till morning probably; but because at the higher temperature of midday, the air can c entiats generally accepted the theory that the electric current does not flow through a wire, but follows the space around it? A. An eleccold air has. It is for this reason that we should have a water pan in the hot-air box of the furnace and add water vapor to the heated air before it enters the room.

(10240) I. N. A. says: May I ask

me to any publication describing such a pu and recommending the circumstances in the less most helpful? Is the following feasible? Given a deep well, say 90 fewater surface, and required to pump a quantity of water for use in building mairrough A (see sketch 1) connected with



inch pipe is 5 feet higher than trough B connected with a 1½-inch pipe. Both pipes are connected below well water surface at a point where each has been coned down to ½ inch diameter and at this point a third short pipe of 1 inch diameter C is connected which opens out into the well water 5 feet below water surface. Pipe C is closed and the whole system filled with water from trough A, which of course will flow out from trough B. Suppose then the level in trough A is kept constant by lifting the water from B to A and pipe C is opened. Will a bigger discharge arrive at trough B than that which is poured into trough A owing to well water entering at C, where, due to the coning, the pressure head has been converted into velocity? Rough dimensions have been assumed only for facility of expression. A. A fet pump works on the principle that a stream or jet of liquid at a high velocity will drive or carry along with it the particles of fluid which surround it. We doubt if it would be possible to make the plan which you show in your sketch work because the difference in level between the reservoir A and the reservoir B is not sufficient to overcome the friction in the pipes. If you made the difference in level 50 feet instead of 5 and properly proportion the nozzles and openings at the point C such a device could be used to raise the water from the well. The inclosed sketch (2) shows the general way in



which these nossles should be proportioned. The end of the supply pipe from the higher reservoir should terminate in a small nossle A from which the water will flow with great velocity. The openings BB and the contracted diameter of the chamber at B' should be small, so as not too greatly reduce the velocity of the water which issues from the nossle at A. A large valve should be supplied at D which is used to start the pump. This is opened wide. After the water is flowing through the nossle with its maximum velocity the valve D is suddenly closed. This will cause sufficient pressure in the chamber above, due to the momentum of the water, to cause it to force the check valve E open. If everything is properly proportioned and if there is sufficient head more water can be forced into the reservoir B than flows from the reservoir A.

(10241) H. L. P. asks: Will you kindly publish in your query column a list of all the different kinds of ether waves, their rate of vibration per second, and their wave lengths, and do they all travel at the rate of 186,000 miles per second? A. The ether waves concerning which you inquire are the vehicle by which the radiations pass from the sun to the earth. These radiations become heat, light, or electro-magnetism, and other forces perhaps, when they strike unon organs which can ap-(10241) H. L. P. asks: Will you when they strike upon organs which can ap-propriate them as such. That which strikes the eye becomes light, that which affects other the eye becomes light, that which affects oth nerves of sensation gives us the sensation theat. You will find much about these matter in Thompson's "Light, Visible and Invisible So far as we know, all these waves parthrough space with the same velocity, about 186,000 miles per second. We can send you the book named for \$2. We can send yo

the book named for \$2.

(10242) A. S. asks: Would you kindly explain to me, in your query column, we have a water pan in the hot-air box furnace and add water vapor to the air before it enters the room.

(40) I. N. A. says: May I ask owing questions of your world-renowned What is a jet pump? Can you refer moves clower would be left behind on the road.



Engine and Foot Lathes MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. BEST MATERIALS. BEST WORKMANSHIP. CATALOGUE FRE SEBASTIAN LATHE CO., 120 Culvert St., Cincinna

Foot and Power and Turret Lathes. Plan SHEPARD LATHE CO. DE W. 20 St. Cincinnati, O

Veeder Counters

co. 18 Sargeant St Hartford, Coun



Taber. Lead-Colored & State Pencils. Rubber Bands. Brasers, Inks. Penholders, Rulers, Water Colors, Improved Calculating Rules. Send for description Oscular S.

44-60 East 23d Street, New York, N. Y. Grand Prize, Highest Award, St. Louis, 1904.

BARKER MOTORS

Reliable.-1% to 10 H. P-Economic

Their perfect operation and reli-bility are due to common sense nechanical ideas and good construc-ion. While low in price, they are nade of best materials with careful itention to details.

G. L. BARKER, NORWALK, CONN.



GRINDER

Automatic Water Supply draulic Engine Co.



Electrical Engineering

and Experimental Work of Every Description
have every facility for producing first-class work
mpily. Our factory is equipped with modern manery throughout.

C. F. SPLITDORF ering Dept. 17-27 Vandewater St., N. Y. City

A Home-Made 100-Mile Wireless Telegraph Set

construction of a liu-mile wireless telegraph outnet. erous, adequate diagrams accompany the text. a 10 cents by mail. Order from your newsdealer, or

MUNN & CO , 361 Broadway, New York

THE EUREKA CLIP and notion dealers, or by mail on receipt of price. Sample card, by mail, free. Man-ufactured by Consolidated Safety Pin Co., Box 131. Bloomfield, N. J.







With reference to a point on the earth, that point with which the wheel is in contact with the earth, the part of the wheel which rests on the ground at the moment is at rest. The top of a wheel moves with a lever-like motion with reference to the point in contact with the earth. Probably this is what you have in mind in your question. It is fully discussed in Notes and Queries of Vol. 93, Nos. 16, 20, and 25, to which we would refer you. We send them for ten cents each.

(10243) G. W. B. asks: Why is it (10243) G. W. B. asks: Why is it that if there is a particle of grease or some other substance on the inside of the glass of a cylinder jubricator, the drop of oil tends to slide away from it, and if there is some substance all the way around the inside of the glass the drop of oil lengthens out and becomes oblong until it passes that substance? A. We presume the phenomenon you have noticed is due to capillarity. The fact that the drop does not wet or come into contact with the side of the tube causes its peculiar motion.

(10244) B. C. J. W. asks: Will you please explain the following questions in Notes and Queries? In Todd's "New Astronomy," page 253, it is stated that even the faintest stars are visible by day and night from the moon. Why is this the case? A. The absence of air from the moon would enable dwellers there to see the stars at all times. The sun would be a blazing star, and its light would not be diffused through space so that it would render other heavenly bodies invisible, as is the case on the earth. Stars may be seen on the earth in the daytime through a telescope, which cuts off the scattered rays of sunlight and allows the rays of the star to come directly to the eye.

(10245) R. W. M. asks: I would like (10244) B. C. J. W. asks: Will you

(10245) R. W. M. asks: I would like (10240) R. W. M. BBKB; I WOULD ING
to know through your paper as to how to make
the best kind of a storage battery with the
following materials: Three lead plates (square)
\$\mathbb{G}\$ x 6\mathbb{G}\$ x 1/16 inch; nine (round) plates 4
inches diameter x \mathbb{G}\$ inch. A. As good a way
as any to make a storage cell from sheet lead
is to be found in our SUPPLEMENT 845, price
ten cents. A much better cell can be made by
following the methods given in SUPPLEMENT
1434, price ten cents.

(10246) J. H. N. asks: What theory theories are held to explain cyclones? Cyclones are large whiriwinds which travel A. Cyclones are large warrivings which tra-over the earth from west to east. The wi-blows into the storm from all sides, so the the whirl of the storm is in a direction op-site to the motion of the hands of a watch the northern hemisphere, as the storm mor-forward. The subject is treated fully Waldo's "Elementary Meteorology," which is send for \$1.75.

NEW BOOKS, ETC.

CONCERTE COUNTRY RESIDENCES. New York: Published by The Atlas Portland Cement Company, 1906. Illustrated; pp. 92.

Rarely does a manufacturing company issue as excellent a book as this one, placed before the public by the Atlas Portland Cement Company. The importance of the subject to the householder doubtless warrants the trouble and expense of publishing as ambitious a work as this. Concrete for residential building purposes is constantly coming into greater utilization, and the many advantages which it possesses are steadily bringing it to the fore for this purpose. A recapitulation of these adseases are steadily bringing it to the fore for this purpose. A recapitulation of these ad-vantages would be unnecessary in this review. The possibilities of concrete can in no way be better demonstrated than by the numerous ex-amples of residences and country houses illus-trated in the book. The diversity of archi-tectural style and construction which is made cossible by the employment of concrete is striktectural style and construction which is made possible by the employment of concrete is strikingly shown in the various types of buildings. The illustrations—and these really constitute the entire text—are of representative rural concrete residences from all parts of the country. The photographs are supplemented by floor plans showing in detail the construction of the buildings. Every house owner interested in this question should procure a copy of "Concrete Country Residences"; a more striking recommendation for this type of building can hardly be found in the literature of architecture. The book is handsomely printed and bound in heavy paper. nd in heavy paper

COUNTRY COTTAGES AND WEEK-END HOMES.
By J. H. Elder-Duncan. New York:
Cassell & Co., Ltd., 1906. 4to., pp.
224. Price, \$2.50.

224. Price, \$2.50.

The layman of moderate means will find excellent information regarding country cottages suited alike to his class and to his purse in this handsome book. The illustrations include half-tones from photographs of actual cottages, as well as floor plans showing in detail the internal arrangements of the buildings. The text is written in non-technical form, and it gives much practical data as regards the possible and actual costs of the buildings illustrated, various points which come into consideration, a short chapter on gardens, and general information, among which the schedule of architect's fees will doubtiess be of service. However, as the cottages in question are English, and were built under the conditions obtaining in England, the circumstances will probably differ somewhat in this country as regards the actual construction. Nevertheless,

Maxwell AUTOMOBILE

Maxwells stand second in number of cars sold during the past year. No more could be sold because no more could be made

Multiple Disc Clutch. Three-point Sus-pension of Motor and Transmission (Unit), Metal Bodies, No Noise. No Vibration. Equipped with Apax Tires guaranteed for 5,000 miles riding.

\$1,450

The Maxwell Catalogue is more than a book Specifications. It is a complete treatise on the coparative merits of the various systems of automot construction. Seat free if you write Dept. 11.

MAXWELL - BRISCOE MOTOR CO.

RUDSON TERRACE, TARRYTOWN, N. Y.

MAIN OPFICE AND FACTORY.

PAWTUCKET, R. L. TARRYTOWN, N. Y. CHOGGO, I.L.

Member American Motor Car Manufacturer' Association, N. Y.

Exhibit at A. C. A. Automobile Show, Grand Cen-tral Palace, New York, December 1st to 8th.

FASTENERS

RNAL WORK OF THE LANGLEY. A painstaking discussion thority on Aerodynamics INTERNAL By S. P. LANGLEY LANGLEY. A painstaking discussion thority on Aerodynamics, of a subject interested in airships. SCIENTIFIC PLEMENTS 946 and 947. Price 10 all. Munn & Company, 351 Broadway, nd all newadealers.



A Desirable Xmas Gift. **Recording Thermometer**

ces automatically a correct and auous record in lak of the tem-are on a graduated weekly chart, in two sizes, and standardized ally guaranteed. Also other re-ug weather instruments.

Instructive Scientific Papers ON TIMELY TOPICS

Price 10 Cents each by mail

ARTIFICIAL STONE. By L. P. Ford, A paper of immense practical value to the architect and builder. SCIENTIFIC AMERI-

CAN SUPPLEMENT 1500.

THE SHRINKAGE AND WARPING OF TIMBER. By Harold Busbridge, An excellent presentation of modern views; fully illustrated. SCIENTIFIC AMERICAN SUPPLEMENT 1500.

CONSTRUCTION OF AN INDICATING OR RECORDING TIN PLATE ANEROID BAROMETER. By N. Monroe Hopkins. Fully illustrated. SCIENTIFIC AND AND AND ASSOCIATION OF THE CONTROL OF THE C

DIRECT-VISION SPECTROSCOPES.
By T. H. Blakesley, M.A. An admirably
written, instructive and copiously illustrated
article. SCIENTIFIC AMERICAN SUPPLE-

MENT NO. 1493.

HOME MADE DYNAMOS. SCIENTIFIC AND ACTUAL OF THE ACTUAL O

PLATING DYNAMOS. SCIENTIFIC AMERICAN SUPPLEMENTS 720 and 793 describe their construction so clearly that any

DYNAMO AND MOTOR COMBINED.
Fully described and illustrated in SCIENTIFIC
AMERICAN SUPPLEMENTS 844 and 865.
The machines can be run either as dynamos

ELECTRICAL MOTORS. Their Con-struction at Home. Scientific American Sufficients 759, 761, 767, 641.

Price 10 Cents each, by mail

MUNN & COMPANY Broadway New York

om a purely architectural standpoint, the

try also.

Text-Book of Fungl. By George Massee. New York: The Macmillan Company, 1906. 12mo.; pp. 427. Price, \$2.

As the author explains, the object of the text-book of fungl is to serve in some measure as an introduction to the comparatively new lines of research opened during recent years in the morphological, biological, and physiological study of fungl, and also to indicate the sources whence information of more detailed kind may be obtained. Our knowledge of this subject has been increased remarkably within the past few decades, and the appearance of this book is both timely and necessary, for the usual text-books discussing the questions involved are on the whole extremely technical and academic.

INDEX OF INVENTIONS

For which Letters Patent of the

United States were Issued for the Week Ending November 20, 1906.

AND EACH BEARING THAT DATE [See note at end of list about copies of the Wessell
Wessell
Wessell
Wessell
W. W. McGrew
Attachment, buggy, W. J. Dolan
block, vehicle. J. Mufr.
tie making machine. C. B. Fost.
ng press, F. A. Byther.
See Foot ball.
detter and feeder, E. U. pown.
detter and feeder, E. U. pown. d cutter and feeder. E. U. Doddages, machine for making oil Paris, J. K. Toles. doleer or belt, L. D. Hubbard. doleer or belt, E. D. Hubbard. ge, steel, A. L. Hofman. tery cell, dry. J. W. Brown-ring for wheels, realilent, A. ring, roller, D. Allen. bottom. E. A. Cleaveland. invalid. W. C. McGough. lock, J. E. Coleman. pan, I. Newman., soffs. R. Delmel. ch. stop. E. H. Sbeldon. ch. stop. E. H. Sbeldon. gag package, A. W. Holway. er. H. W. Mewes. 836,182

stop, E. ta.
package A. W. Hotwa,
R. W. Mowes.
H. W. Mowes.
L. W. Mortele.
L. W. Mowes.
L. W. Mordele.
L. W. M. M. Mordele.
L. W. M. W. M. W. M. Bushy.
L. W. M. 836,127 836,218

and shoes, detachante twent Busby implement, J. F. & W. G. Piet E. M. Smith, Jr. ... cleaning apparatus, E. Weymar measuring, W. T. Seers non-refillable, H. C. Keithler ies aning apparatus, E. Series. Sec. 466
le non-redillatie, H. C. Keithler. Sec. 36, 869
elet, J. Bennett. Sec. 36, 869
elet, O. L. Gammelgaard. Sec. 36, 690
elet, O. L. Gammelgaard. Sec. 36, 690
elet, O. L. Gammelgaard. Sec. 36, 106
e apparatus, load, Mason & Farmer. Sec. 106
e apparatus, load, Mason & Farmer. Sec. 106
e lever, Dunn & Whitaker. Sec. 46, 640
te mechnism, J. H. McCormick. Sec. 26, 640
te mechnism, J. H. McCormick. Sec. 26, 640
te mechnism, J. H. McCormick. Sec. 26, 640
der beater. G. E. Littlefield. Sec. 46, 640
der beater. G. E. Littlefield. Sec. 164
der, poultry, E. J. Hudson. Sec. 250
kle. W. Bloomberg. Sec. 250
kling block machine, E. F. Sanford. Sec. 250
ung fuel, J. M. Schutz. Sec. 250
kling block machine, C. F. Sanford. Sec. 250
dy machine, T. Aliatt. Sec. 250
dy machine,

Carriage, folding baby, N. Kalli.
Cattle stock, B. G. Labachotte.
Cement block machine, Yoocum & Cramberg
Cement bulking block, Layfield & Crisp.
Cement post, L. H. Stoner.
Chimney closure and ventilator, J. E. Nei-

tte michnate controlling keyboare
Delany
Delany
F. R. Elbert
Cleanaing device, W. S. Baker
sa line reel, S. C. Goldenberg
a. find speed governing, J. C. Waods,
a, roller friction, A. C. F. Dann
gaa, W. N. Fynes
e pot, J. A. Cox.
rocat Day, C. H. Stonebridge, 836,411
gaible nor, C. H. Stonebridge, 836,411
sutomatic locking, C. V. J. Christ
automatic locking, C. V. J. Christ
Controlling C. W. Christ
Con

Any Size or Shape Steel Towers Any Height The Baltimore Cooperage Co.

MANUFACTURERS
BALTITIORE CITY, MD.

CATALOGUE GRATH

It's Easy to Keep (ool! The simplest, smallest, safest, nearest and most successful Motor Fan made is the Rawlings Putcut High-Speed Water Motor Fan, Can be installed in a few

E. GINTZEL 150 Nassau St., New York City





CENTRAL MANTEL CO., 12180live Str. St. Louis "Economo" Emery Wheel Dresser

SCIENTIFIC AMERICAN MUNN & CO., 361 Broadway, N. Y. BRANCH OFFREE: 625 F St., Washington, D.C.

Convert Bicycle Into Motorcycle



at small cost by attaching the self-starting EHIE 2 H. P. Power Outst.
This includes all parts by

MOTORCYCLES





Three Hone Power. Simplest materievele on the market. Agents wanted everywhere. Catalog free. THE THOMAS AUTO-BI (4).

1450 Niagara Street

Buffalo, N. Y.



PS. USE GRINDSTONES P The CLEVELAND STONE CO.

"Christmas Comes But Once & Year"

This year you needn't deny yourself the pleasure of giving liberally.

If you're short of cash:

\$12.50

Herbert L. Joseph & Co

State Street :: CHICAGO





speaking, personality. Send for Free Bookle Dickson MINGRY SCHOOL, 100 Kimbell East, CH-Cas S80 TO S175 PER MONTH



The Genuine Armstrong's and DIES

Asknowledged to be the beet. Different sizes and capacities. Write for catales.

THE ARISTRONG MPG. CO., Bridgeport, Comm. New York Office, 120 Contra Street.



THE CURTIS A CURTIS CO., 6 Garden St. . Namespress, Co. New York Office, 60 Contec 86.

Machine No. 26, Rango 236-4 in, R. H.

SPARK COILS

Their Construction Simply Explained

Scientific American Supplement 160 describes the making of a 1½-inch spark ooil and condenser.
Scientific American Supplement
1514 tells you how to make a coil for gas-

engine ignition.

Scientific American Supplement
1522 explains fully the construction of a
jump-spark coll and condenses for gas-angine


Scientific American Supplement 1124 describes the construction of a 6-inc spark coil Scientific American Supplem 1087 gives a full account of the making an alternating current coil giving a 5

Scientific American Supplement 1527 describes a 4-inch spark coll and col


denser. Scientific American Supplement 1402 gives data for the construction of odd of a definite length of spark.

The above-mentioned set of seven papers will be supplied for 70 cents.

Any single copy will be mailed for 10 cts. MUNN & COMPANY, Publishers 361 Broadway New York



Block Machine





Its Manufacture Its Denaturization Its Industrial Use

The Cost of Manufacturing Denaturized Alcohol in Germany and German Methods of Denaturization are discussed by Consul-General Frank H. Mason in SCIENTIFIC AMERICAN SUPPLEMENT 1550. The Use, Cost and Efficiency of Alcohol as a Fuel for Gas Engines are ably explained by H. Diederichs in SCIENTIFIC AMERICAN SUPPLEMENT 1596. Many clear diagrams accompany the text. The article considers the fuel value and physical properties of alcohol, and gives details of the alcohol engine wherever they may be different from those of a gasoline or crude oil motor.

oil motor.

In SCIENTIFIC AMERICAN SUPPLEMENT 158; the Production of Industrial Alcohol and its Use in Explosive Totors are treated at length, valuable statistics being given of the cost of manufacturing alcohol from farm products and using it is a constitution. om farm products and using it in engines. French Aethods of Denaturization con-

stitute the subject of a good article published in SCIENTIFIC AMERICAN SUPPLE-

ow industrial Alcohol is flade and

How Industrial Alcohol is I'ade and Used is told very fully and clearly in No. 3, Vol. 95, of the SCIENTIFIC AMERICAN.

The Most Complete Treatise on the Modern Manufacture of Alcohol, explaining thoroughly the chemical principles which underlie the process without too many werrisone technical phrases, and describing and illustrating all the apparatus required in an alcohol plant is published in SCIENTIFIC AMERICAN SUPPLEMENTS 1603, 1604 and 1605. The article is by L. Baudry de Saunier, the well-known French authority.

de Saunier, the well-known French authority.

In Supplements 1607, 1608, 1609 we publish a digest of the rules and regulations under which the U. S. Internal Revenue will permit the manufacture and denaturation of tax free alcohol.

The Sources of Industrial Alcohol, that is the Farm Products from which alcohol is distilled, are enumerated by Dr. H. W. Wiley in Scientific America. America America 1611 and 1612 and their relative alcohol content compared.

In Scientific America Supplement 1613 the uses of Industri 1 Alcohol in the Aria and in the Home are discussed.

Any Single Number of the Scientific American or Supplement will be sent for 10 cents by mail. The entire set of papera above listed will be mailed on receipt of \$1.40.

Order from your newsdealer or from the

MUNN @ COMPANY 361 Broadway, New York

L. Talbott. Dunn W. Aletter Daniels tos press and tecoses; Cumpston . ch, invalid's, J. W. Bess. ss bearer, A. E. Ostrander. sabers and pulvertisers, dumping cage for, M. F. Williams . S80, 161 to 886, 163, inary utensii, J. H. Collins. Whimatensil, J. H. Co.
L. D. Tucker......
B. D. McGuire...
tree, G. B. Reye...
Bundy & Manwaring.
h, G. H. D. Ross...
weezers, W. W. Bur
Laweezers, W. W. Bur
Laweezers, W. W. Bur 836,209

S. apparatus for circulating liquids SS6,101 clubw anthracene, Schmidt & Tunt SS6,220 f. J. Callahan SS6,000 with the SS6,000 currents, means for controlling the bly of. F. W. Schnelder. SS6,337 circuit switch, Seavey & Millen. SS6,239 currents, means for controlling the bly of. F. W. Schnelder. SS6,279 tabe lighting, D. M. Moore, reisene 12,561 with the seave of the ctrical attachment plugs and the like, cap for, F. E. Seelegher, F. E. Seelegher, F. J. Tone.

J. Tone.

trodes for electrical accumulators by means of continually working machines, manufacture of, B. W. Jungner...

vator door safety attachment, Gill & Mechan guite and scoop board for wagons, E. P. Jung and S. G. Harmer and scoop board for wagons, E. P. June, A. G. Harmer and scoop board for wagons, E. P. June, A. G. Harmer and scoop board for wagons, E. P. June, A. G. Harmer and scoop board for wagons, E. P. June, A. G. Harmer and scoop board for wagons, E. P. June, A. G. Harmer and scoop board for wagons, E. P. June, A. G. Harmer and scoop board for wagons, E. P. June, A. G. Harmer and scoop 836,155

A. G. Heggem. S56,186
aparking igniter, gas, H. A. Johnsgarking igniter, gas, H. A. Coleman less explosion, C. J. Coleman less automatic cut off device for, Hegle & Peterson less ignition device for explosion, A. Clement 836,254

836,093

ingines, ignition device for explosion, A. Clement
togines, lighter bar frame for rag, E. A. Peterson
vener, Moe & Norblom.
xeavating machinery, W. Ferris.
xeavator, G. W. King.
yeglass guard, L. P. Adt.
yeglass mounting, W. E. Aruold,
yeglass mounting, McKee & Offedahl...
eed for steam boliers, automatic, de La
Rochefoucalid & Meland.
...
heep for the steam boliers, automatic, de La
rectification of the steam boliers, J. Collar,
errule driver, apple hole, B. Woerner,
ertilizer distributer, W. J. Elson.
Dickinson
bers and other particles from waste water,
apparatus for recovering, C. BacheWug 836,458 836,197 836,248 836,118 836,076 836,236 836,598 836,126

Dicknowledge of the particles of the par

Garner devine apparatus for ore, J.
Hickop & H. K. Christ.
Game, W. J. Roche.
Game apparatus, H. E. Christ.
Game table, A. V. Rush.
Garbage can, M. C. Blrnie.
Garbage furnace, W. F. Morse.
Garten, B. Garten, B. Kusche.
Garter, D. Brondbelt.
Garbage furnace, W. F. Morse.
Garter, D. Brondbelt.
Garbage furnace, W. F. Morse.
Garter, D. Brondbelt.
Garbage furnace, Controller for use in connection
with the ignition of, V. C. J. Nightingdish burners, device for lighting by electricity reversed, P. Bernard.
Gas generator, G. Gerrard.
Gas generator, acetylene, M. F. McNelly.
Gas generator, acetylene, C. A. King.
Gas lighting mechanism, time, N. F. Englund.

tund
s, preparing solutions of, H. Howard
L. Woolard.
cutter, J. Voss.
s insulators or other glass articles, making, H. M. Brookheld
s insulators or other similar glass articles, apparatus for making, H. M.
Brookheld

overhor for gasolene engines, Cormack & Zumdabl
Zumdabl
Zimdabl
Zimdab

They Men

hey carefully. Have you ever known a man with technical training fitting him for any one of these positions who was out of employment or not receiving a good salary? Of course not! Then think how independent the same training would make you.

You can get this training without leaving home or loss of time from present employment by the wonderful system of instruction of the International Correspondence Schools. You only need write and say which of the following occupations you would like to be fitted for.

Mechanical Draughtman, Citil Engineer, Chemist agineer,

Read over the list

Mechanical Draughtemas, Civil Engineer, Chemist, Textile Hill Supt., Electrician, Electrical Engineer, Mechanical Engineer, Telephone Engineer, Electric Lighting Supt., Surveyor, Stationery Engineer, Build-ing Custractor, Architectural Draughteman, Architect, Bridge Engineer, Struct'l Engineer, Hinley Engineer,

Bridge Engineer, Mrade'l Engineer, Mining Engineer.
Full details of the plan costs you nothing. The instruction that will mean your success in life will cost you but little, either in time or money. Is it not worth an inquiry?

Factory Clerks and Superintendents

We can help you to increase your earning power from 25 to 50% by means of our Course of Instruction in COST ACCOUNTING. We can teach you not only to devise and instal a system for the place you now fill, but to build factory systems for others. In fact we can teach you to become a COST EXPERT. Hundreds of our students are to-day filling the best positions. Do you want to be helped as we have helped them? Let us show you how we do it. It costs must nothing to investigate. The cost is small and we give you all the time you want in which to pay it. A few of your spare half hours for the next few months will put you in a position to demand far more salary or to produce far better results. There is no way to advance except through knowledge. Let us teach you. Drop us a postal card and ask for our plan for teaching you how to become an

Expert Cost Accountant

The International Accountants' Society, Inc. 59 FORT STREET, DETROIT, MICHIGAN



INNER TUBES

Obviate Tire Troubles

STRONGEST TUBES Imported or Domestic

PARKER, STEARNS & CO. 228 and 229 South St., New York, U. S. A.



Yours very truly,
BRENNAN STANDARD MOTOR Transmission.

Motors from 6 to 80 Horse Power



CHAS. J. JAGER CO.
281 Franklin, cor. Batterymarch St.,
Boston, Mass.

For the Assembler and Repairman Prices on all makes of w Establishment January are moving the goods, for snaps.

Write for snaps.

NEUSTADT AUTOMOBILE & SUPPLY CO.

826-830 S. 18th St., St. Louis. Mo.




Stallman's Dresser Trunk Easy to get at everything without disturbing anything. No fatigue in packing and unpacking. Light, strong, roomy drawers. Holds as much and costs no more than a good box trunk. Hand-riveted strongest trunk made. In small room serves as chiffonier. C.O.D. with pre-case trunk made. P. A.STALIMAE, GI. W.Spring St., Glumbus, O.

To Book Buyers

We have just issued a new 112-page catalogue of re-cently published Scientific and Mechanical Books, which we will mail free to any address on application.

MUNN & COMPANY ublishers of Scientific American
361 Broadway, New York



Machines

g, simple and durable. Any mechanic te them easily. Send for catalog. WILLIAMS BROS., Ithaca, N. Y.

Concrete, Reinforced Concrete Concrete Building Blocks

atific American Supplement 1548 contain ticle on Concrete, by Brysson Cunning e article clearly describes the proper sition and mixture of concrete and ults of chaborate tests.

cientific American Supplement 1538 gives the proportion of gravel and sand to be used in concrete.

centific American Supplement 1534 gives a critical review of the engineering value of the reinforced concrete.

cientific American Supplement 1574

steel for reinforced concrete.

clientific American Supplements 1875, 1876, asi
1877 contain a paper by Philip L. Wormler
Jr., on cement mortar and concrete, theli
preparation and use for farm purposes. The
paper exhaustively discusses the making of
mortar and concrete, depositing of concrete,
facing concrete, wood forms, concrete side
walks, details of construction of reinforced
concrete posts.

Each number of the Supplement costs

A set of papers containing all the article above mentioned will be mailed for \$1.80.

Order from your newsdealer or from

MUNN @ CO. 361 Broadway, New York City

Classified Advertisements

Advertising in this column is 50 cents a line. No less than four nor more than ten lines accepted. Count seven words to the line. All orders must be accompanied by a remittance. Further information sent on request.

SALE AND EXCHANGE.

FOR SALE.—Engine Lathe, swings %4 in. takes 25 in. between centers; complete with full set change gears to cut all size threads, 3 to 40 in.; price only \$41.00. Address L. F. Grammes & Sons, Allentown, Pa.

FOR SALE—United States and Canadian patents The world's best surf-actuated motor. The only Motowith sufficient regularity for dynamo operation with sufficient regularity for dynamo.

BUSINESS OPPORTUNITIES.

FOR SALE.—Portable Compressed Air House Cleaning Wascons and Machinery sold to responsible parties to operate in cities of from five thousand inhabitants upwards. Each Portable Cleaning Plant has an earning wards. Each Portable Cleaning Plant has an earning wards. State of Form \$6.00 to \$70.00 per day, at a cost of about \$6.00 per day. Capital wards along the state of the wards. State of the property of the wards and the property of the property of the wards and the property of the wards and the property of the wards and the wards are the property of the wards and the wards are the property of the wards and the wards are the wards and the wards and the wards are the wards of the wards and the wards are the wards of the wards of the wards and the wards of the war

HOW TO SELL STOCK—IF YOU WANT CAPITAL send stamp for my booklet, "How to Seal Stock;" telis how capital is secured, how to reach investors by mall, by advertising, by personal solicitation; how to get investors' names, how to write prespectus, Cash A. Harris, 676, I Madison Avenue, New York.

LEARN Scientific Business Letter Writing by mall from man who built up half-a-million-dollar business. Big demand for good correspondents. Prospectus free Page-Davis School of Letter Writing, Dept. 88, Chicago.

I SELL PATENTS.—To buy or having one to sell, write thes. A. Scott, 719 Mutual Life Building, Buffalo, N. Y.

NEWEST DIRECTORY OF CIGAR AND TOBACCO Manufacturers, Leaf Tobacco Dealers, etc. Price \$8 For further information address Tobacco Leaf Publishing Co., 53 Beaver Street, New York.

MOTION PICTURE MACHINES, Film Views, Magic Lasterns, Slides and similar Wonders For Sale. Catalogue Free. We also Buy Magic Machines, Films, Slides, etc. T. S. Harbach, 500 Filipert St., Fhiladelphia, Pa.

offi. 10. Halves FOR A CAPITALIST with \$10,000, to share control with inventor and squip factory for making an absolutely waterproof, satisfary and fadeless wallpaper at reasonable prices.

The state of the state

WATER STILL.—Fits any Tea Kettle. Guaranteed one to two quarts per hour. Without kettle \$2.00. Express prepaid in United States \$2.50. Adams Co., 3.6 West Polk Street. Chicago.

WANTED.—Superintendent to take charge of small plant for manufacturing mechanical specialties and machinery. Must have practical experience in modern shop methods. Write giving full experience and salary required. Superintendent, Box 773, New York.

all kinds. Best equipment, Send sketch or model for estimate, stating quantity. Hayes Manufacturing Co., 45.75 Maybury Avenue, Detroit, Mich.

profit; we are not patent lawyers. Boston School of Inventing, P. O. Box 2003, Boston, Mass. Particulars free.

Typewriters.—All makes, all prices. Twelve stores in principal cities. Catalogue and address of nearest store sent on request. The Typewriter Exchange Company, Dept. A, 35: Broadway, New York.

AUTO CAR PRACTICE.—"Homans' Self-Propelled Vehicles." 1907 edition just issued, right up to date, is the most complete book on the motor car practical, fully illustrated, 60 pages, handsomely bound. "Foot wanted Specimen pages free upon request. For full particulars and information address Theo. Audel & Co., 65 lifth Avenue, New York.

TYPEWRITERS

TYPEWRITERS OUR OWN MANUFACTURE full guaranteed at special prices to those who will recommend the American to their friends. American Type writer Co., 261 Broadway, New York.

POSTAL Typewriter \$25. Only real typewriter at low cost. Combines Universal Keyboard, strong manifolding, mimeograph stencii cutting. Visible writing, interchangeable type, prints from ribbon. Imperfect alignment impossible. Will stand hardest wear; practicalignment impossible. Will stand hardest wear; practically accident proof. Agents wanted. Write Fostal Typewriter Co., Dept. 77, Nowwalk, Conn.

TYPEWRITERS.-For a minister, lawyer, literary man of woman, or any person who writes, or for people who wish to learn a desirable and lucrative occupation, son you imagine a more acceptable gift than a No. 3 sun Typewriter, at \$40.07 sent upon examination to reserve the sent of the property of the property of address many property of the property of the property. New York.

HELP WANTED.

DRAFTSMEN.—Are you looking for advancement to you want to get off the board? Hundreds of posttions for capable men at \$900.42,500. Write us to-day. Hapgoods, 300 Broadway, New York.

UNUSUALLY GOOD SALARIES and a strong demand for men in the photo-engraving business. The wunderful increase in the use of illustrations in all newspapers and magazines creates an unlished call for men to turn out outs. Twenty-dre considered to the control of the control of the You can learn the control of the control of You can learn the control of the control of August 1997 of the control of Photo-Engraving, 466 Pearl Street, corner Park Sow, New York.

WANTED.—Competent Draughtsman and Designer with experience in handling men, for position with machine shop. Salary \$4.50 to \$4.30 per year depending on experience, Apply to Draughtsman, Box 773, N. Y.

PATENTS FOR SALE.

AUTOMOBILE PATENT FOR SALE - Protects damaged tires, prevents skidding. Sure of big sale, Made cheaply, Not able to manufacture. Will sell patent or on toyakly. G. Adams, 100 Spruce St., St. Louls, Mo. OFFERS INVITED FOR PURCHASE OF UNITED States Patent overing novel and useful device for feeding horses. Botter than nose bags. Wm. Oliver.

FOR SALE.—Valuable patent in plumbing line. Will sell all or part interest. Stand thorough investigation. Large profits can be made. Address Patent, 917 Seventh Avenne, New York.

FOR SALE.—U. S. Patent No. 811,322 granted Jan. 1906, on Collapsible Canopy for launches. Excellent opportunity for party with manufacturing appliances Address John Poltock, East Rutherford, N. J.

PATENTS SOLD ON COMMISSION. If you wish to buy or soll a patent write for particulars to E. L. Perkins, 72 Broad Street, Boston. Patent Sales Exclusively.

DRAMATIC.

TOUNG MEN WANTED to learn stage management, and the stage date of the stage of the

PARTNERS WANTED

WANTED,—Partner with money to manufacture and place upon market Razor Stropping any one can useddoes quick work—bears good profit. For full particulars address H. P. Fowler Pelbam, S. C.

EXPERIMENTAL WORK.

JOHN F. PITZ, INC., 99 FRANKFORT ST., makers of patterns and models. Every facility for aiding inventors to perfect their ideas. Large and small contracts executed promptly. Machine patterns a specialty.

MACHINERY FOR SALE.

If interested in power for any kind of light manufacturing, electric lighting, marine or other purposes, acinformation on the most improved kerosene oil engine by sending for catalogue to Hemington Oil Engine Co. 41 rdrs Ro.

STEAM BOILERS.

THE RECORD of the Hogan Water Tube Bolier proves it the safest, most reliable and efficient steam generator known. Built only by James Dean, Ridge-Beid Park, N. J. Information for the asking.

FACTORY AND MILL SUPPLIES.

FACTORIES, CUT DOWN TOUR INSURANCE by putting in a Caldred Tank and you got far protection. Once up, no further expenses of far protection. Once up, no further expenses in every section. Arkay Stave Co., of Columbus, Miss, says: "Saves us 830 a month." Illustrated Catalogue and Price Last

BOOKS AND MAGAZINES.

MAGAZINES, Newspapers and all periodicals at lowest club prices. Our catalogue contains a list of 3,000 periodicals and combination offers. A handy magazine guide, 42 pages and cover, sent Free for the askingbennetive Magazine Agonoy, 68 Le Salie St., Caicagofili.

| Hat fastener, J. J. Dukote. Hay knife, T. Spriggs. Hay loader, H. O. Univer, reissue. Hay rake, C. Pearson | 836,183 836,541 12,564 836,206 836,171 836,282 836,451 836,451 836,457 836,457 836,457 836,469 836,400 |
|--|--|
| Webber 1 Webber 1 Webber 2 Webber 2 Webber 2 Webber 2 Webber 2 Webber 2 Wilcox Incubator G. Hacker G. Hacker Induction coll apparatus, E. C. Wilcox Inhaler, pocket, C. P. Moore. Ink well, J. A. Cunningham Insulator, electric outlet, J. E. Moore Insulator, high potential, F. M. Locke. Jewel setting, W. B. Allen. Journal box, antifriction, D. Allen. Keybox Instruments, finger key for, O. C. | 1 1 1 1 |
| Knife polishing device, H. J. Hutchinson. Label holder, dispensing, J. Bryniidsen. Ladder and Ironing board, combination step, H. B. Haley. | 836,385 836,189 836,086 836,112 836,111 |
| Lamp shade, detachable incandescent, H. D'Olier, Jr | |
| Keyboard instruments, Inger key for, O. C. Kayle | 836,490 836,144 836,574 836,290 836,360 836,358 836,147 |
| C. W. Conner. C. W. Conner. Letter, electric sign, H. B. Camp. Leveler and scraper, road, C. W. Kauffman Life havious processes and the scrape of the level. Life avious processes and the leveler of the leveler. Life bolder, J. F. Koepp. Line bolder, J. H. Kidny. Linotype machine, P. T. Dodge. Linotype machine, adjustable liber for, L. Ward Liquid discharging device, H. & C. G. | 836,486 836,088 836,506 836,174 836,524 836,114 836,193 836,506 836,374 |
| Ward Liquid discharging device, H. & C. G. | 836,349 |
| Liquid discharging device, H. & C. G. Nichols Liquid fuel burning furnace, E. H. Peabody Lock and latch, J. Longe, Lock and latch, J. Longe, Lock and latch mechanism, H. G. Voight. Lock mechanism, H. G. Voight. Lock mechanism, Caley & Volght. Lock mechanism, Caley & Volght. Locomotive pilot, F. W. Renner. Loom, pile fabric, E. S. Craddock. Looms, device for holding thrums or knotting threads in, E. Marschner. Lubricating device, F. W. Hall. Lubricator, Matson & Baldwin. Lubricator, Matson & Zeyen. Lubricators, distributer for force feed, E. H. Mikins. | 836,335 836,529 836,515 836,289 836,288 836,300 836,535 836,305 |
| threads in, E. Marschner. Lubricating device, F. W. Hall Lubricator, Matson & Baldwin, Lubricator, Matson & Zeyen Lubricators, distributer for force force | 836,518 836,253 836,195 836,234 |
| Mantle supports, forming, C. M. Lungren. Match asfe, C. Pickard. Mattress, J. M. Kinyon. Measuring machine, automatic, J. Froelich Mechanical movement, N. Howard. Metal pipe, cast, R. P. Barnstead. | 836,200 836,123 886,139 836,326 836,185 836,579 836,173 |
| Metal working machines, tool feed mechan- ism for, D. L. Chandler Micrometer for measuring the thickness of | 836,631 |
| paper and other sheets, H. F. Provandie Mill. See Rolling mill. Mills, ppeumatic hobbin converse. | 836,605 |
| Metal working machines, tool fee 856,419, mechanism for, D. L. Chandler. Micrometer for measuring the thickness of paper and other sheets, H. F. Provandle Mill. See Rolling mill. Mills. paeumatic bobbin conveyer for, P. J. Hanlon the stackment, W. N. Brown. Mirer for concrete, cement, or other substances, W. J. Judd. Mixing machine, W. J. Judd. Molding mechanism, I. A. Perjue. Molding or electric wire conductor, W. H. G. Kirkpatrick. | 836,320 836,481 836,378 |
| mixing machine, W. J. Judd | 836,190 836,191 836,277 |
| Motor starting switch, T. von Zweigbergk. Music chart, A. B. Fitch. Muszle, A. W. Swender. | 836,121 836,342 836,115 836,427 836,570 836,413 836,458 |
| Napkin holder, G. W. Peters. Nut lock, D. Tarbox Nut lock, A. B. Keene. Orange clipper, J. G. Kyle. Ore separator, A. J. Bauer. Ores, etc., automatic drying apparatus for, | 836,152 836,507 836,388 836,553 |
| J. Hickey. Ores, treating, W. A. Hendryx. Ornamentation, protecting the inside of vessels during the process of, E. L. Toy | 836,187 836,380 836,415 |
| Oven, sectional, R. Crawford. Packing, ro'ary shaft, W. F. Somes. Pail, oyster, W. Seyser. Paper boxes, machine for making necks for | 836,245 836,408 836,499 |
| | 836,399 836,336 |
| Paper feeding machine, G. R. Williams. Paper folding machine, J. H. Adams Parer, vegetable, O. P. G. Radach | 836,637 836,164 836,235 836,140 |
| Paper rouging machine, J. H. Adams. Parer, vegetable, O. P. G. Badach. Pen, blotter, and other appliance, combined fountain, Lurye & Lewis. foundain, Lurye & Lewis. Pen, self illing fountain, B. Conklin. Pen, Pen, P. R. Brupe. | 836,516 836,180 836,149 |



Just Published

The New Agriculture

By T. BYARD COLLINS

12mo, 374 pages, 106 illustrations, cloth, price \$2.00

HIS new and authoritative work deals with the subject in a scientific way and from a new viewpoint. Dr. Collins has devoted his lifetime to the study of changing economic agricultural conditions. "Back to the soil" was never a more attractive proposition and never so worthy of being heeded as during these opening years of the twentieth century. Farm life to-day offers more inducements than at any previous period in the world's history, and it is calling millions from the desk. The reason for this is not at first obvious, and for this reason Dr. Collins has prepared the present work, which demonstrates conclusively the debt which agriculture owes to modern science and the painstaking government and State officials. Much of the drudgery of the old farm life has been done away with by the use of improved methods, improved stock and varieties. All this tends to create wealth by increased value of the product and decreased cost of production. Irrigation, the new fertilization, the new transportation, the new creations, the new machinery, all come in for a share of attention. The illustrations are of special value, and are unique. All who are in any way interested in agriculture should obtain a copy of this most timely addition to the literature of agriculture. A full table of contents, as well as sample illustrations, will be sent on application.

MUNN & CO., "Betentific American," 361 Broadway, New York

Valuable Books Photographic paper, self-tening, Home Mechanics for Amateurs







MAGIC Stage Illusions and Scientific Diver-



This work appeals to old and young alike, and it is one of the most attended to the year. The lillusions are lillustrated by the thishest class of engravings, and the exposes of the tries are, in many president class of engravings, and the exposes of the tries are, in many president and the engravings, and the exposes of the tries are, in many president and the engravings, and the exposes of the tries are, in many president and the engravings of the engravings are of the engraving and the engrave and the engravement of the engraveme

JUST PUBLISHED

Scientific American Reference Book

12mo. 516 Pages. Hinstrated. 6 Colored Plates. Price \$1.50, postpaid



Photographic paper, soft tosing, G. S. Poul-sen
Photographic printing machine, G. N. Wins-low
Plane attachment, automatic, J. A. Smith, relasue 836,461 Photographic proming machine, d. A. Binith, reliesare primary by electrolysis, producing, E. D. Chaplin a strachment, automatic, J. A. Binith, reliesare primary by electrolysis, producing, E. D. Chaplin Chaplin C. W. Morris. S36,197 Platte retailer, C. W. Morris. S36,197 Platten of 4200 copies has been considered. It is seen to be subjected to be supported by the supporting device, W. Maxfield. S36,322 Plants supporting attachment. For one-constitution, was a supported by the support of the

TWENTY-THIRD EDITION
EXPERIMENTAL SCIENCE
By GEORGE II. HOPKINS

Resided and Gravity Enthrory. 20 Celar Debund. 1,100
Pages. 300 History to Clear Debund. 2, 100
Pages. 300 History to Clear Debund.

The work against problems of the problems of t

THE WORLD'S WORK for 1907









Not a scrapbook, and not a fiction magazine, The World's Work tells the human stories of every month's greatest activities, and illustrates them with an unequalled richness of clear and interesting photographs. It is a record of all the inportant things that go in politics, business, education, books, art, human achievement. In the coming year will appear:

THE WORKINGS OF THE TRUSTS: A remarkable series of articles by Mr. C. M. Keys, unveiling the methods, secret and open, of these colossal creations—showing just where they are benefits and just where they are benefits and just where they are present.

DOES H'AR VARD DO ITS
JOB? Not Harvard alone, but Yale,
Princeton, and other colleges. A series
showing how our universities are doing what ct of them

We expect of them.

MEDICAL SENSE AND NONSENSE. The death-rate has been lowered but life shortened. Marvellous discoveries
have been made. This series will bring home
to every man and woman the ways in which
life can be lengthened.

WHAT OTHER COUNTRIES
CAN TEACH US. Stories of the
things they do better in England, France,
Holland, Germany, Canada, Japan.

continue.

THE MEN WHO ARE MAKING TODAY. That mysterious figure,
Mr. E. H. Harriman, explained. The real
Taft, "Secretary of Peace," shown as he is.
Other notable Americans pictured and ana-

lyzed.

THE SECRET OF BUSINESS SUCCESS. Not a series on business forms and office methods, but intimate revelations of big business men laying their plans and fighting their battles, showing how they get their results.

INVESTING YOUR MONEY. Regular monthly articles that will tell investors, big and little, what they want to know about sound investments.

These are but a few of many timely features. Wideawake Americans need this magazine. SUBSCRIBE NOW. 25 cents a copy, \$3.00 a year.

Send your name on a postal and receive further details of special interest.

Doubleday, Page @ Company

133 EAST 16th STREET, NEW YORK









On almost every GOOD Car

You'll see



ins ready-generated Acetylene Gas ready

Forty hours light at the turn of a key. Tanks last FOREVER. No bother. No trouble. No Carbide. No Water. No Dust.

Just pure white light at the turn of a key.



THE PREST-O-LITE CO., Dapt. 18, India

Personally Conducted clusively First-Class-to California-January 10th, February 7th and March 2nd under the auspices of the tourist department, Chicago, Union Pacific and North-Western Line;

ns ey

۲.

It is

oks

City

Include all expenses

-hotels, railway fare, sleeping car and dining car accommoda-tions of the finest character, and numerous side trips. So arranged as to spend the disagreeable portions of the winter months in comfort and ease.

Write for itineraries and full particulars to S. A. Hutchinson, Manager, 212 Clark Street, Chicago, Ill.

ARITHMETIC

SELIFDo not despair because through nexteet, you through nexteet, you have forgotten what you once learned about Arithmetic. Padr. Spangerner about the state of the control of the cont GEO. A. ZELLER HOOK CO. 43 South 4th St., St. Louis, Mo.





MONEY MAKING MACHINE

nickels for its ownection to the public

PHOTOSCOPE Takes one's photograph and pressly framed haide of a minute make a peofit of \$100 a day withere are crowds. Write for and price list.

M. S. KLINE

STUDY High Grade INSTRUCTION By CORRESPONDENCE LAW



60 YEARS'

Scientific American.

Telephone exchange system, semi-automatic, J. M. Thomson, relssue...

Telephone exciting system for, W. Telephone receiver switch, J. McMishon...

Telephone relays and transmitters, regulating device for, H. E. Shreeve. 886,611. Telephone system, F. B. Parker...

Telephone system, F. B. Parker...

Telescope, prism, E. Neumayer...

Trimble, J. L. & Sauvage...

Ticker transportation J. F. Ohmer...

Telescope, and the state of the st ol, convertible machine, T. F. Timby, ob holder, C. J. Fancher. S86,154, or holder, signallug, T. G. Hitt. signallug, T. G. Hitt. signal, Clark & Bennett. swers, anchor for skeleton, D. B. Scholes, F. B. H. Holden. or holder, or holder, cack fastener, C. H. Tibbetts. action wheel, J. Sweney, amway, elevated electric, G. G. Schroeder musers support, B. F. Parris. Lek bolster, cast A. Stucki. description and method and apparatus for forming the same, J. W. Reno. fring implement, J. Bercha.

Tunnel capatractors and metros aparatus for forming the same, J. W. Heno
Turing implement, J. Bercha.
Type distributing machine, F. McClintock.
Typewriter attachment, J. A. Ruffin.
Valve, G. A. Blake.
Valve, S. Schuessler.
Valve, automatic, H. S. Pinkerton.
Valve, edicting, Hobber & Mayer.
Valve, reducing, Hobber & Mayer.
Valve, reducing, H. F. Cunning.
Valve, safety, O. Tittelbach.
Valve, thermostatic, J. H. Davis.
Vehicle brake, E. F. Bradley. S36,084,
Vehicle, dumping, J. Hovas.
Vehicle fonder, automatic, A. P. Smith, Jr.
Vehicle on a line of way or railway, means
for controlling the movements of a, F.
E. Kinsman.
Vehicle apring, M. L. Senderling. 836, 12

12,566 836,340 836,302 836,361 836,578 Vebrice wheel, S. B. Childs.

Vehicle wheel, S. B. Childs.

Vehicle wheel, J. Bolick.

Vehicle wheel, M. H. de Horn.

Vehicles, steam heating apparatus for, H. Gardes. Vehicle wheel, M. H. de Hora.
Vehicles, steam heating apparatus for, H. Gerdes
Vehicles, steam heating apparatus for, H. Gerdes
Vending machine, the H. Palver.
Vending machine, the hoperated, A. Spear.
Ventilating device, N. L. Friese.
Ventilator. See Car or the like ventilator.
Viscose, producing lustrous threads, etc.,
from, M. Muller
Visc. machine. H. F. Kellemen.
Voting machine. A. W. Welble.
Wagon running gear, metallic, A. N. Calkine.

kins and gear, metallic, A. N. Calkins and the state of 836,213 836,600 836,184 836,158 836,119

Wave power generating apparatus, J. A. McManus.

Wax stripper, Fleming & Pedersen.

Whip manipulator, A. L. Weeks.

Winch, G. W. King.

Winding and spinning machine, yarn, Nelid & Marsh.

Winding machinery, hall, J. Mackle.

Windmill, D. Doty.

Window, door, and ventilator, L. Y. McConnell

window fastening device, J. H. Cook.

Were strainer, T. F. Locks.

Wire stretcher, J. H. Heisey.

Wire stretcher, J. H. Heisey.

Wire stretcher, J. H. Gaskill

Wrapping machine, T. L. Camp.

Wrench, S. B. Cochran.

Wrench, C. L. Fortlin.

Yeast mixer, C. Daum.

DESIGNS.

Kieran nedy & King. receptacle, W. J. Moon...

TRADE MARKS.

Healy 57.62: Tires for vehicles, rubber, Baker & Hamilton 57.62:

LABELS.

PRINTS.

"Antomobile Back, Bleycle Playing Cards."
for playing cards, United States Playing
Card Co. 1,842
"Base Balls." for base balls, A. J. Reach Co. 1,842
"Combination Suits," for boys clothing, David
Jacobs 1,841
"Men's and Boys' Apperel," for men's and
boys' apparel, H. C. Lytton. 1,840

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1805, will be furnished from this effice for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 201 Broadway, New



STRONG & DURABLE

The New York Standard

CHRONOGRAPH

IS THE ONLY "Stop-Watch" Watch

made in America and is un-equaled for Laboratorial and Experimental Work, Photo-graphic Purposes, Electric and Telephone Uses. For Refiners and Compounders of Oils, etc. For Physicians, Surgeons, Nurses, and for the exact timing of all athletic events.

All Jewelers Sell Them

New York Standard Watch Co., 401 Communipaw Ave., Jersey City, N. J.



LET US BE YOUR FACTORY
WRITE FOR ESTIMATE ON ANY ARTICLE
YOU WANT MANUFACTURED
STAMPINGS. MODELS, EXPER. WORK
WRITE FOR FREE ROOKLET
THE CLOBE MACHINE A STAMPING CO.
970 Hamilton Bt., Cleveland, O.

Our Filters Purity, Duodot
Decolurius. Bookiet Fve
Bukring Water Puritying
68 Murray St., New Yor Water

"KNIPE" BALL BEARINGS

For thrust or weight or both,
All Riting, last push them on.
All Riting, last push them on.
All Riting, last push them on.
PRESED STEEL MFG. CO., 545 The Source, Phila., Pa.

AUTOMOBILE INSURANCE

FREE ELECTRIC BOOK

plans by which you can accure any article in our catalog absolutely free. Write to-day—don't miss this chance. J. Andrea & Sons Co., 124 W. Water Street, Milwaukec, Wis.

AFG. CO. 80 Cinton St., Milwaukee, Wis.

MODELS & EXPERIMENTAL WORK
To be seen a serious developed, Special Machinery
E. V. BAILLARD, 24 Frankfort Street, New York.

RUBBER Expert Manufacturers
Fine Jobbing Work
PARKER, STEARRS & CO., 238-239 South Street, New York

GEO. M. MAYER, 1131 MONADNOCK, CHICAGO WORKING DRAWINGS

STEEL STAMPS, LETTERS & FIGURES

Specialties & Patents Bought and Sold

BUBIER's "How To Make" Library A Transformer, by L. Millon, Fn.B. & A Consensor and a Layden Jor, by T. E. O'Donnell, E. E. Sand for Bubler Publishing Co., Box S, Lynn, Mans.

Experimental & Model Work

NOVELTIES & PATENTED ARTICLES

NIENTORS We manufacture METAL SPE-LARTERS of all kinds, to order largest equipment: lowest price model for low estimate and best expert advicer REE THE EAGLE TOOL (Co., Bept. A. Christmant, O.

MASON'S NEW PAT. WHIP HOISTS

WATER-WORKS

of the City of Gra

income.

Ids will be received for both wire was a way to be a consequence of the twelve-turn of which shall be wire wound.

In many be seen, and specifications obtained at the coffice of the City Clerk of Grand Junction. Colorado, or the offices of Willard Young and Frank C. Reisey, il Engineers, Salt Lake City, Utah. A bond furnised by a surety company will be required for twelved by a surety company will be required for twelvery count, of the contract price. The time stated in the oposal for completing the work will be considered in completing the work will be considered.

The right is reserved to reject any or all bids or to ward separate contract for the pipe line and for the reservoirs.


JOHN M. CONLEY, City Clerk.

MR. INVENTOR, send us your models of

Start A Mail Order Business.

Acknowledged by shrewd business men con of the most piessant and profitable business in the World. Most work in the World. Most work in the World.





Magical Apparatus.

MODEL ENGINES

MODEL ENGINES

SEND IN FOR 28 PAGE

LE DATE, DOLLE



EARN WATCHMAKING

ST. LOUIS WATCHMAKING SCHOOL

LEARN PLUMBING A few mon struction at or opted by principal storebouses in New York & Boston after graduating. Write bodgy to 1822 11.70 and by YOLNEY W. MASON & CO., Inc., TATED CALLOGUE ST. LOTTE TRAINS CHOOL, 3072 Ulive Street, St. Louis, Market and Control of the Street, St. Louis and Control of the Street, St. Louis and Control of the St. Louis and Control



Rubber Elevator & Conveyor Belting

FOR CONVEYING AND LIFTING BROKEN STONES, COAL, COKE, WOOD PULP, GRAVEL, SAND, SUGAR, etc., etc.

> SPECIAL CONSTRUCTION EXCEPTIONAL QUALITY

NEW YORK BELTING & PACKING CO., Ltd.

91-93 CHAMBERS STREET, NEW YORK



IF YOU OWN A ROOF, USE



PREPARED R. H. MARTIN,
SBESTOS FIBRE OFFICE, ST. PAUL BUILDING 220 B'way, New York.

Ail varieties at towest prices. Seat Hailro Track and Wagon or Stock Scales mand a season of the sea



Calendar Watch

Price. \$7.45



Bausch & Lomb Prism Field Glasses

SEND TO-DAY FOR DESCRIPTIVE CIRCULAR
BAUSCH & LOMB OPTICAL CO.
Rochester, N. Y.
NEW YORK BOSTON WASHINGTON
CHICAGO BAN FRANCISCO



TO PAYS BIG Motion Pictures
To amuse the Motion Pictures





Attained Excellence

Built to satisfy the requirements of the tourist, the Peerless Limousine adapts itself to all conditions. Featured in the Limousine are all the improvements of our 1907 product. Several new features have been added to make the Peerless car still higher in quality and even more thoroughly reliable:

Model 16, \$5,000

3. Larger cylinders, more power,
4. Simple speed control,

The most refined and exacting taste finds in this car every requirement perfectly filled. Luxurious comfort and adequate protection; richness of finish and appointments; ease of entrance and egress; safety and responsiveness of control; reliability, stability, durability

1907 Limousine

Model 16 45 000

Model 15, \$6,000

A booklet describing the new Limousine, and general catalogue P of 1907 Models will be sent on request.

PEERLESS MOTOR CAR CO., 2447 Oakdale Street, Cleveland, O.

The Youth's Companion The Best Christmas Present for \$1.75



ntertainment and Information or Every Member of the Family Every Week

CHRISTMAS PRESENT OFFER.

Every new subscriber who cuts out and sends this slip (or mentions this publication) with \$1.75 for The Companion for the fifty-two weeks of 1907 will receive GIFT 1. 1906, including the beautiful Double Holiday Numbers.

GIFT 2. The Companion's Four-Leaf Hanging Calendar for 1907, in Twelve Colors and Gold, for Companion Subscribers Only.

The Compar in gives as much reading in the year as would fill twenty 400-page novels or books of history or biography ordinarily costing \$1.50 and SEND FOR SAMPLE COPIES AND ILLUSTRATED ANNOUNCEMENT, FREE \$15,200 in cash and many special awards to subscribers who get now subscription. Bond for information

THE YOUTH'S COMPANION, BOSTON, MASS.

STEAM USERS

The original and only genuine red sheet packing.

The only effective and most economical flange packing in existence.

Can't blow Rainbow out.

For steam, air, hot or cold water, acid and ammonia joints.

Beware of imitations.

Look for the trade mark—the word Rainbow in a diamond in black, three rows of which extend the full length of each roll.

Manufactured exclusively by PEERLESS RUBBER MFG. CO. 16 Warren St., New York

UNIVERSITY SHOE

Send for pamphlet J. P. TWADDELL, 1816-1818 Market St., Philadelph



Something you need to know about.





LUFKIN TAPES AND RULES

LUFKIN RULE CO. Saginaw, Mich., U. S. A. New York and London.



HANDSOME PROFITS

are realized by growing pheappies Porto Rico. Our copperative plan all non-residents to obtain plantaties small monthly payments. Large ans returns and absolute security. No fro no tariff, cheap labor and cheap freight if you want to know all about beauti-send for free booklet.

LA FORTUNA FRUIT CO.

1 Madison Ave. New York

The Good Power




C. Gasoline Engine puts you right am in the power question. A complete in se facts will serve your interest we too by writing for our engine catalog

The Way to Get Out of a Hole Is Not to Get into It.



GENERAL LIBRARY, UNIV. OF MICH. DEC 8 1908

ARMOR WITH AIR GENERATING EQUIPMENT FOR DEEP SEADIVING:



The House Founded On A Rock

Shall stand. Build your fortunes on the rock foundation of Life Insurance. It has shielded thousands from want, educated thousands of young men and women, and started them in business. Write to-day for information of Policies, with Rates and Benefits at your age. Address Dept. 121.

The Prudential Insurance Company of America

Incorporated as a Stock Company by the State of New Jersey

JOHN F. DRYDEN, President

HOME OFFICE: Newark, N. J.

The buildings pictured above are owned and occupied by The Prudential Insurance Company of America, as its Home Office at Newark, N. J. The extensive business of The Prudential requires in these home office buildings alone, the services of over two thousand employees.